

15-00903022-0500


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Location as Barton County, Sec. 8 Twp. 16 Rge. 11 E/W
"NE/CNW 1/4 SW 1/4" or footage from lines
W/2-NE/NE

Lease Owner Roxana Corporation
Lease Name O'Leary Well No. 2
Office Address Box 611, Great Bend, KS 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Oil
Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed 6-23 19 78
Reason for abandonment of well or producing formation

Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	406'	None
				4 1/2"	3278'	1285.78

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Shot tubing at 2160', 2056', 1300'
Pulled 43 joints tubing.
Dumped sand to 1400' and 4 sacks cement.
Shot casing at 1400'
Pulled 40 joints 4 1/2 casing
Plugged with 4 sacks hulls, 15 sacks gel mixed with 1 sack hulls, 100 sacks 50/50 poz w/4% gel

RECEIVED
STATE CORPORATION COMMISSION
6-27-78

JUN 27 1978

(If additional description is necessary, use back of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold
James W. Rockhold Box 698, Gr. Bend, KS
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 26th day of June, 1978

Cathy L. Cole
Notary Public.

My commission expires

STATE NOTARY PUBLIC
KANSAS
CATHY L. COLE
Barton County, Kansas
My Appt. Exp. 6-24-82

WILKINSON DRILLING, INC.
 1121 Union National Building
 Wichita 2, Kansas

February 5, 1958

O'LEARY NO. 2

Company	- WILKINSON DRILLING, INC.	Location	- W/2 NE NE, Sec. 8-16-11W
Contractor	- Company Tools		Barton County, Kansas
Commenced	- October 28, 1957	Elevation	- 1793 GL
Completed	- November 8, 1957	Casing	- 20 fts. 8 5/8"
Total Depth	- 3282 feet		102 fts. 4 1/2"

FIGURES INDICATE BOTTOMS OF FORMATIONS

Depth	Formation
0 - 40	Sand Rock
40 - 370	Clay and Shale
370 - 390	Blue Shale
390 - 665	Shale and Red Beds
665 - 690	ANHYDRITE
690 - 875	Shale and Shells
875 - 1385	Red Beds, Shale, and Shells
1385 - 1610	Shale and Shells
1610 - 1740	Shale, Lime, and Pyrite Streaks
1740 - 2115	Lime and Shale
2115 - 2720	Shale and Lime
2720 - 2750	Lime
2750 - 2920	Lime and Shale
2920 - 3247	Lime and Shale Streaks
3247 - 3269	Various Colored Shale and Chert
3269 - 3274	Cherty Dolomite
3274 - 3282	Dolomite

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 02 1978
 CONSERVATION DIVISION
 Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the O'Leary No. 2, located in the W/2 NE NE, Section 8 - 16 - 11W, Barton County, Kansas.

WILKINSON DRILLING, INC.

Subscribed and sworn to before me this fifth day of February, nineteen hundred and fifty-eight.

Notary Public

My commission expires January 2, 1961.