


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-009-03023-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 8 Twp. 16 Rge. 11 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE/NW/NE



Locate well correctly on above  
Section Plat

Lease Owner Roxana Corporation  
Lease Name O'Leary Well No. 3  
Office Address Box 611, Great Bend, KS 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) Oil  
Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 5-17 19  
Plugging completed 6-27 19  
Reason for abandonment of well or producing formation Depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	393'	None
				4 1/2"	3278'	2073.03'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand to 2750' and four (4) sacks of cement.  
Shot at 2500', 2320' and 2120'.  
Pulled 66 joints of 4 1/2" casing.  
Squeezed with 2 sacks hulls, 25 sacks gel w/ 1 sack hulls, and 100 sacks 50/50 poz w/ 4% gel.

RECEIVED  
STATE CORPORATION COMMISSION  
6-27-78  
JUN 27 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CONSERVATION DIVISION  
Wichita, Kansas  
Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
James W. Rockhold Box 698, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of June, 1978

My commission expires

STATE NOTARY PUBLIC  
CATHY L. COLE  
Barton County, Kansas  
My Appt Exp June 14, 1982

Cathy L. Cole  
Notary Public.

15-009-03023-0000

WILKINSON DRILLING, INC.  
1121 Union National Building  
Wichita 2, Kansas

February 5, 1958

O'LEARY NO. 3

Company	- WILKINSON DRILLING, INC.	Location	- NE NW NE, Sec. 8-16S-11W
Contractor	- Company Tools		Barton County, Kansas
Commenced	- November 11, 1957	Elevation	- 1796' KB
Completed	- November 21, 1957	Casing	- 20 jts. 8 5/8" @ 393
Total Depth	- 3500 feet		104 jts. 4 1/2" @ <del>3284</del> 3278

FIGURES INDICATE BOTTOMS OF FORMATIONS

Depth	Formation
0 - 120	Post Rock and Clay
120 - 300	Clay and Shale
300 - 390	Blue Shale
390 - 610	Shale and Red Beds
610 - 695	ANHYDRITE
695 - 1360	Shale and Shells
1360 - 1725	Shale and Lime
1725 - 2060	Lime and Shale
2060 - 2755	Shale and Lime
2755 - 2946	Lime and Shale
2946 - 3257	Lime and Shale Streaks
3257 - 3264	Sandy Shale
3264 - 3278	Various Colored Shale and Chert
3278 - 3280	Dolomite

RECEIVED  
STATE COMPLETION COMMISSION  
APR 06 1978  
CORRELATION DIVISION  
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the O'Leary No. 3, located in the NE NW NE, Section 8 - 16S - 11W, Barton County, Kansas.

WILKINSON DRILLING, INC.

Subscribed and sworn to before me this fifth day of February, nineteen hundred and fifty-eight.

Notary Public

My Commission expires January 2, 1961.