


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

BARTON County. Sec. 8 Twp. 16 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C N/2 S/2 SE/4  
Lease Owner PETROLEUM, INC.  
Lease Name NEY Well No. 3  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 21, 1957  
Application for plugging filed September 23, 1957  
Application for plugging approved September 21, 1957  
Plugging commenced September 21, 1957  
Plugging completed September 22, 1957  
Reason for abandonment of well or producing formation  
No producible zone  
If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege Hoisington, Kansas  
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3351 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	362'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud up with heavy mud to 330' pushed down 1/2 sack hulls to 330'.  
Followed by wooden plug, Placed 20 sacks cement through drill pipe on to plug. Mud up to 25' pushed down 1/2 sack hulls to 25', Followed by wooden plug and 5 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Don Searle (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle  
Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1957

L. J. Brown  
Notary Public.

My commission expires July 11, 1960

PLUGGING  
FILE SEC 8 T 16 R 11 W  
BOOK PAGE 48 LINE 2

9-27-57

# WELL LOG

15009-06287-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 8 T. 16S R. 11W

FARM NEY NO. 3


LOC. C-N/2 S/2 SE

TOTAL DEPTH 3351'

COUNTY Barton Co., Kansas

COMM. September 13, 1957 COMP. September 22, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 362' W/200 sax.

ELEVATION 1841' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Post rock
363	Shale
1350	Shale & shells
1755	Shale & lime
2070	Lime
2245	Shale & lime
2480	Shale
2685	Shale & lime
2836	Lime
2936	Lime & shale
2978	Sand & shale
3287	Lime
3351	Conglomerate shale.
3351	T. D.

State of KANSAS  
County of BARTON } ss:

**PLUGGING**  
FILE SEC. 8 T. 16 R. 11W  
BOOK PAGE 48 LINE 2

9-27-1957  
DIVISION  
Kansas

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #3 Ney well

Verne A. Morris

Subscribed and sworn to before me this 25th day of September 19 57

My Commission Expires: July 11, 1960

Jed A. Brown  
NOTARY PUBLIC