


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 8 Twp. 16 Rge. 11 (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Lewis Drilling Company, et al
Lease Name Ney Well No. 2-A
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned
Date well completed 9-6-49 19
Application for plugging filed 3-31-51 19
Application for plugging approved 3-31-51 19
Plugging commenced 4-1-51 19
Plugging completed 4-3-51 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 12-30-50 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3303 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	189'	None
				5-1/2"	3281'	2462'
				Lane Wells Plug @ 3036'		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from Lane Wells plug at 3120' to 3050' and ran 5 SX cement. Mudded hole from 3000' to 189' set 10' rock bridge and ran 15 SX cement. Mudded hole to 25', set rock bridge and ran 5 SX cement on top. Well completed.

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1951
5-21-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lewis Drilling Company
Address 607 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Hiram W. Lewis, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hiram W. Lewis, Jr.
607 Union National Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of April, 19 51.

Arthur P. Derrington
Notary Public.

My commission expires August 20, 1952.

PLUGGING
FILE SEC-8 T-16 R-44
BOOK PAGE 71 LINE 37

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

15009-071900000

COMPANY Lewis Drilling Company, et al

SEC. 8 T. 16 R. 11

FARM Ney

NO. 2-A

LOC.

SW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$

TOTAL DEPTH 3303'

COUNTY Barton

COMM. 8-25-49


COMP. 9-6-49

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10	
15	8-5/8"	187'
12	6	
13	5	

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	85	Post rock and sand
85 -	425	Blue shale
425 -	470	Sand
470 -	520	Shale
520 -	550	Red bed
550 -	685	Red bed, shale and shells
685 -	710	Shale and shells
710 -	735	Anhydrite
735 -	965	Red bed, shale and shells
965 -	1055	Salt, shale and shells
1055 -	1100	Salt
1100 -	1390	Shale and shells
1390 -	2095	Brown lime
2095 -	2100	Lime and shale
2100 -	2595	Shale and shells
2595 -	2795	Lime and shale
2795 -	2865	Lime
2865 -	3005	Lime and shale
3005 -	3270	Lime
3270 -	3288	Lime chert
3288 -	3303	Cherty lime and shale
3303 -	TD	

GEOLOGICAL TOPS

Lansing-Kansas City	2992
Erosional Arbuckle-Chert	3279
Arbuckle Dolomite	3300

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

Hiram W. Lewis, Jr., Lewis Drilling Company, of lawful age, being first duly sworn under oath, states that the Lewis Drilling Company was the Contractor engaged for the drilling of the Ney No. 2-A, located in the Southwest Quarter of the Northeast Quarter of the Southwest Quarter (SW $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$) of Section 8, Township 16 South, Range 11 West, Barton County, Kansas, and that the foregoing log is a true and correct copy of the log of the completed well.

LEWIS DRILLING COMPANY

By Hiram W. Lewis, Jr.
Hiram W. Lewis, Jr.

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, this 11th day of May, 1951.

Arthur P. Harrington
Notary Public

My commission expires August 20, 1952.

PLUGGING
FILE SEC. 8 T. 16 R. 11W
BOOK PAGE 74 LINE 37