


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 8 Twp. 16 Rge. 11 (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Lewis Drilling Company, et al
Lease Name Ney Well No. 3-A
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned
Date well completed 10-3-49 19
Application for plugging filed 3-25-51 19
Application for plugging approved 3-25-51 19
Plugging commenced 3-26-51 19
Plugging completed 4-1-51 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 12-30-50 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	190'	None
				5-1/2"	3362'	2226'
				Lane Wells Plug at 3036'		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from Lane Wells plug at 3036' to 3000'
and ran 5 SX cement. Mudded hole from 2950' to 200',
set 10' rock bridge and ran 15 SX cement. Mudded hole
from 145' to 30', set rock bridge and ran 5 SX cement
on top. Well completed.

FILED
STATE CORPORATION COMMISSION
MAY 21 1951
CONS. DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lewis Drilling Company
Address 607 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Hiram W. Lewis, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hiram W. Lewis, Jr.
607 Union National Bank Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of April, 19 51

Arthur P. Derrington
Notary Public.

My commission expires August 20, 1952

PLUGGING
FILE SEC 8 T 16 R 112
BOOK PAGE 71 LINE 18

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

75-009-07191-0000

COMPANY Lewis Drilling Company, et al

SEC. 8 T. 16 R. 11

FARM Ney

NO. 3-A

LOC. NW SE SW

TOTAL DEPTH 3400'

COMM. 9-21-49

COMP. 10-3-49


COUNTY Barton

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20 10
15 8-5/8" 181'
12 6
13 5

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 181 Surface sand and clay
181 - 300 Blue shale and red bed
300 - 710 Red bed and shells
710 - 770 Anhydrite
770 - 1275 Shale and shells
1275 - 1490 Shale, shells and brown lime
1490 - 1720 Brown lime
1720 - 1885 Lime and shale
1885 - 2150 Brown lime
2150 - 2705 Lime and shale
2705 - 2890 Lime
2890 - 2985 Lime and shale
2985 - 3285 Lime
3285 - 3360 Lime and shale
3360 - 3371 Shale
3371 - 3400 Lime
3400- ED

GEOLOGICAL TOPS

Lansing-Kansas City 3087
Conglomerate 3301
Arbuckle 3371

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

RECEIVED
STATE CORPORATE DIVISION
MAY 21 1951
CONSERVATION DIVISION
Wichita, Kansas

Hiram W. Lewis, Jr., Lewis Drilling Company, of lawful age, being first duly sworn under oath, states that the Lewis Drilling Company was the Contractor engaged for the drilling of the Ney No. 3-A, located in the Northwest Quarter of the Southeast Quarter of the Southwest Quarter (NW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$) of Section 8, Township 16 South, Range 11 West, Barton County, Kansas, and that the foregoing log is a true and correct copy of the log of the completed well.

LEWIS DRILLING COMPANY

BY Hiram W. Lewis, Jr.
Hiram W. Lewis, Jr.

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, this 11th day of May, 1951.

Arthur P. Derrington
Notary Public

My commission expires August 20, 1952.

PLUGGING
FILE SEC 8 T. 16 R. 11
BOOK PAGE 71 LINE 18