

15-009-151600000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County. Sec. 8 Twp. 16 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NE

Lease Owner National Cooperative Refinery Association

Lease Name Lizzie Muller Well No. 1

Office Address 820 Union National Bank Building

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 14, 1945

Application for plugging filed January 28, 1953

Application for plugging approved January 28, 1953

Plugging commenced April 3, 1953

Plugging completed April 13, 1953

Reason for abandonment of well or producing formation Production depleted.

If a producing well is abandoned, date of last production January 5, 1953

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3180 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	240'	Cemented
				5 1/2"	3330'	2416'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Rocked hole from 3180' to 2840' and ran 5 sacks cement. Fill hole with heavy mud from 2790' to 238', set 10' rock bridge plus 20 sacks cement. Mudded hole to 30', set rock bridge, dumped 10 sacks cement on up to base of cellar.

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1953
WICHITA, KANSAS


STATE OF Kansas COUNTY OF Sedgwick W. Jean La Coss (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean La Coss

820 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of April, 19 53

My commission expires June 30, 1954
C. Orville May Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15009-1516 0000

Company - BLACK-MARSHALL OIL CO.
Farm - Lizzie Muller No. 1.

SEC. 8 T. 16 R. 11 W
SW SE NE

Total Depth. 3335
Comm. 7-27-45 Comp. 8-7-45
Shot or Treated.
Contractor. Ferrell-Young Drlg. Co.
Issued. 9-22-45

County. Barton
KANSAS



Elevation. _____

Production. Phy.Pot. 192 B

CASING:

10" 238' Cem.
5 1/2" 3330' Cem.

Figures indicate Bottom of Formations.

cellar	4
shale & shells	490
red rock & shale	725
anhydrite	755
shale & shell	1195
shale & salt	1370
shale & lime shells	1450
shale & lime	1875
lime	1975
shale	2000
lime & shale	2180
shale & shells	2615
shale & lime	2835
lime	2950
shale & lime	3021
lime - Kans City	3150
lime	3224
lime & shale	3306
lime & shale (chert)	3317
conglomerate (chert)	3330
Arbuckle	3335
Total Depth	

Tops:

Anhydrite	725
Kans. City	3019
Cherty Congl.	3317
Arbuckle	3330

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 16 R 11 W
BOOK PAGE 26 LINE 3

PLUGGING
FILE SEC 8 T 16 R 11 W
BOOK PAGE 26 LINE 30