

*2/3 in file*

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

15009-23003-0000

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 8 TWP. 16 RGE. 11 E/W  
Location as in quarters or footage from lines:  
50' N - SW/SW/NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner The Roxana Corporation  
Lease Name O'Leary "B" Well No. #4  
Office Address Box 1162 - Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced May 18, 1983  
Plugging completed June 1, 1983  
Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gib Scheck

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3271'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	326'	NONE
				4 1/2"	3267'	2471.33'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Dumped four (4) sacks cement, sanded to 3200' and dumped four (4)  
sacks cement. Shot pipe @ 2670', and 2540'.  
Pulled fifty-nine (59) joints 4 1/2" casing.  
Sun Oil Well squeezed with four (4) sacks hulls, twelve (12) sacks gel,  
sixty-five (65) sacks 50/50 pozmix cement with 4% added gel and 3%  
calcium chloride, three (3) sacks gel, one (1) sack hulls, released  
plug and pumped one hundred (100) sacks 50/50 pozmix cement with 4%  
added gel and 3% calcium chloride. Shut in at 600 psi.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 13<sup>th</sup> day of June, 1983

My Commission expires: \_\_\_\_\_  
Margaret Prosser  
Notary Public.



JUN 14 1983  
6-14-83  
CONSERVATION DIVISION  
Wichita, Kansas