

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,205

LEASE NAME Wirth -0000

WELL NUMBER "B" #1

SPOT LOCATION S/2 S/2 SW

SEC 8 TWP.16 RGE.11 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 3-27-84

Plugging Completed 4-27-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Roxana Corporation

ADDRESS Box 1850, Great Bend, Ks. 67530

PHONE # (316) 792-3072 OPERATORS LICENSE NO. 6284

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	379'	None
				5-1/2"	3347'	2,460.71'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped 5 sacks cement on bottom. Sanded to 3100' and dumped 5 sacks cement. Shot casing at 2600' and 2500'. Pulled 56 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 9 sacks gel, 80 sacks cement and 6 sacks gel blended with 1 sack hulls. Released plug and pumped 70 sacks 50/50 Pozmix cement with 10% added gel and 3% calcium chloride. Maximum pressure was 1000 psi and shut in 500 psi

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well and the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1984
4-30-84
CONSERVATION DIVISION
Wichita, Kansas

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED James W. Rockhold before me this 27th day of April, 1984

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton-County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

(Signature) Iona M. Leatherman
Notary Public