


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 9 Twp. 16 Rge. 11 (K) W (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Petroleum, Inc.
Lease Name Davidson "B" Well No. 1
Office Address Route 2, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed May 31 19 58
Application for plugging filed May 31 19 58
Application for plugging approved May 31 19 58
Plugging commenced May 31 19 58
Plugging completed May 31 19 58
Reason for abandonment of well or producing formation No producible zones

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas
Producing formation ----- Depth to top ----- Bottom --- Total Depth of Well 3274 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	430'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud up with heavy mud to 350' followed by wooden plug. Placed 25 sacks cement through drill pipe on to plug, followed by 1/4 sack hulls.
Mud up to 40' followed by wooden plug and 1/4 sack hulls. 10 sacks cement to base of well cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1958
6-12-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garveyn Drilling Co.
Address Route 2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Don Searle (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1958

Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC. 9 T. 16 R. 11 W
BOOK PAGE 105 LINE 9

WELL LOG

15009-06288-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 9 T. 16 R. 11W

FARM DAVIDSON "B" NO. 1


LOC. SW, NW, NW

TOTAL DEPTH 3274'

COUNTY BARTON CO., KANSAS

COMM. May 23, 1958 COMP. May 31, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 430' W/250 sax.

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

105	Sand & shale
255	Shale
413	Shale, iron & sand
635	Shale
664	Anhydrite
1720	Shale & shells
2948	Lime & shale
3249	Lime
3274	Shale & lime
3274	T. D.

FILED
STATE CORPORATION COMMISSION
JUL 2 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 9 T. 16 R. 11W
BOOK PAGE 105 LINE 9

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING CO.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 DAVIDSON "B" well

Subscribed and sworn to before me this 10th day of June 19 58

My Commission Expires: July 11, 1960

Verne A. Morris
Jed T. Brown
NOTARY PUBLIC