

15-009-06470-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Barton County, Sec. 9 Twp. 16S Rge. 11W (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NW SW

Lease Owner. Black Marshall Oil Co.

Lease Name. Hulda Davidson Well No. 1-B

Office Address. Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed. July 17, 1945 19

Application for plugging filed. July 17, 1945 19

Application for plugging approved. July 19, 1945 19

Plugging commenced. July 17, 1945 19

Plugging completed. July 18, 1945 19

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr

Producing formation. None Depth to top. Bottom. Total Depth of Well. 3278' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	165	175'	8 5/8"	210'	Cemented with 85 Sacks.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

~~Heavy mud/was/~~

Hole was filled with heavy mud up to 204', the hole was then bridged with a wood plug at 200', then 20 sacks of cement was run on top of the wood plug, then the hole was filled with heavy mud to 20', where a bridge was set and 15-sacks of cement run on top of bridge to bottom of cellar and cellar cemented.

PLUGGING
FILE 9-16R/114
BOOK PAGE 20 LINE 19



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Black Marshall Oil Co.

Address. Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton

Walter C Roberts (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter C Roberts

Clafin, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 1945

Elwin Woydzick

Notary Public.

My commission expires February 5, 1947

15-009-06 4700000

COMPANY: Black-Marshall Oil Company
CONTRACTOR: Ferrell-Young Drilling Company
FARM: Davidson "B" #1

LOCATION: NE 1/4 SW 1/4
Section 9-16S-11W
Barton County, Kansas

COMMENCED: July 6, 1945
COMPLETED: July 17, 1945

CASING RECORD:
8 5/8" 204' 85 Sx

ELEVATION: 1787

FORMATION	DEPTH	TOPS:	
Cellar	4		
Shale & Shells	165		
Sand	175		
Shale & Shells	440		
Red Rock & Shale	645		
Anhydrite	665		
Shale & Shells	1200	Anhydrite	645
Salt & Shale	1800	Lensing	2955
Shale & Shells	1615	Conglomerate	3227
Lime	1625	T. D. (Conglomerate)	3278
Lime Broken	1705	D & A	
Lime	1955		
Lime & Shale	2650		
Lime	2670		
Shale	2954		
Lime	3227		
Conglomerate & Shale	3247		
Conglomerate Chert	3264		
Chert & Shale	3272		
Chert & Conglomerate	3278		
Total Depth	3278		

I hereby certify this to be a correct and accurate log of the above described well as shown by the drilling report.

FERRELL-YOUNG DRILLING COMPANY

BY: *James J. Huff*
JUL 24 1945

Subscribed and sworn to before me this 24th day of July, 1945.

Carmen Reinhardt Weber 7-26-1945

My commission expires: February 19, 1949.

DRILLING
FILE 9-16R-11W
LOG 20 LINE-19