

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

JAN 3 1962
Rec'd 1-3-62

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Hamilton County, Sec. 2 Twp. 24 Rge. 39 (E7) (W)

Location as "NE/CNW%SW%" or footage from lines 1250' from S & E Lines

Lease Owner D. W. Marden

Lease Name Thomeczek Well No. 2-2

Office Address 16 W. 1st St., Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Nov. 12 19.61

Application for plugging filed Nov. 13 19.61

Application for plugging approved Nov. 13 19.61


Plugging commenced Nov. 13 19.61

Plugging completed Nov. 14 19.61

Reason for abandonment of well or producing formation Too much fluid (water) for small amount of gas (50 MCF)

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation None Depth to top Bottom Total Depth of Well 2515' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Possible Tert. watersand	?	96	118	8 5/8	287'	None
" " " "	?	174	182	8 5/8	287'	None
" " " "	?	201	208	8 5/8	287'	None
" " " "	?	220	228	8 5/8	287'	None
" " " "	?	245	252	8 5/8	287'	None
Krider Gas dolomite	Non-commer. gas	2428	2447	4 1/2"	2515'	950'
Winfield " "	" " "	2480	2498	4 1/2"	2515'	950'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

2515-2512 Cement not drilled out
2512-2402 River sand
2402-2380 Bridge with coarse rock & 5 sacks of cement

Shot off 4 1/2" casing & pulled 950', leaving 1565' casing in hole.

2380-290 Rotary mud
290-270 Bridged off with coarse rocks & 20 sacks of cement

Note: Well was not plugged from 270' to surface at farmer's request who wants to make a water well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Edico Driller's, Inc.
Address 401 N. Princeton, Liberal, Kansas

STATE OF Kansas, COUNTY OF Hamilton, ss.
Douglas W. Marden (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Douglas W. Marden
16 W. 1st St. Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of December, 1961

My commission expires Sept 7 1964

Notary Public



LEASE: THOMASZEK #2-2
 OPERATOR: D. W. HARMON
 CONTRACTOR: EARL P. WAKEFIELD
 COMB: 10-10-61 COMP: 10-14-61

LOCATION: C SE
 SECTION 2-248-39W
 HAMILTON COUNTY, KANSAS
 CASING: 8 5/8" Set at 282'
 4 1/2" Set at 2522'

Surface Sand	87
Sand, Clay, Blue Shale	301
Shale	425
Shale, Red Bed, Anhydrite	1165
Red Bed	1190
Anhydrite	1215
Shale, Anhydrite	1305
Shale	1550
Anhydrite, Dolomite	1695
Anhydrite, Shale	1830
Shale and Anhydrite	1952
Anhydrite - Cima.	1965
Shale	2080
Shale and Lime	2370
Anhydrite with Shale	2460
Shale and Dolomite	2522
T.D.	2522

RECEIVED
 STATE CONSERVATION COMMISSION

FEB 7 1962

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the THOMASZEK #2-2 well, located C SE, Section 2-248-39W, HAMILTON COUNTY, KANSAS.

EARL P. WAKEFIELD

By F. J. Bacher

Subscribed and sworn before me this 23rd day of October, 1961.

My commission expires:
January 25, 1965

Frank H. Filey
 Notary