

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-093-00387-00-00

LEASE NAME BAUMGARDNER

WELL NUMBER #1

2640 Ft. from S Section Line

2640 Ft. from E Section Line

SEC. 36 TWP. 24S RGE. 38 (E)er (M)

COUNTY Kearny

Date Well Completed Oct. 1949

Plugging Commenced 8/6/2001

Plugging Completed 8/7/2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR OSBORN HEIRS COMPANY

ADDRESS P.O. BOX 17968, San Antonio, Texas 78217

PHONE# (210) 826-0700 OPERATORS LICENSE NO. 5249

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by District # 1 office (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? no log run

Producing Formation Chase Depth to Top 2494 Ft. Bottom 2670 Ft. D. 2670 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase	Gas & water	0		10 3/4		
		0	2484	7"	2484'	0
		0	1970	4 1/2"	1970'	1930'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ foot to \_\_\_\_\_ foot each set.

SEE REVERSE SIDE FOR DETAILS OF PLUGGING

Name of Plugging Contractor Superior Servicing Inc. License No. 32297

Address P.O. Box 772, Liberal, Kansas 67905

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OSBORN HEIRS COMPANY

STATE OF TEXAS COUNTY OF BEXAR, ss.

Nancy A. FitzSimon, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Nancy A. FitzSimon  
(Address) Nancy A. FitzSimon, Engineering Manager

SUBSCRIBED AND SWORN TO before me this 18th day of January XXI 2002

Mary J. Castoreno  
Notary Public

My Commission Expires: \_\_\_\_\_

RECEIVED

JAN 22 2002  
1-22-2002  
KCC WICHITA



Form CP-1  
Revised 05-88

OR

**Plugging Record:**

This well had 4 1/2" casing run inside 7" casing from surface to 1970 ft. The plugging plan included pulling the 4 1/2" casing out of the well so that cement could be placed inside and outside the 7" casing above 700 ft. The condition of 7" casing would dictate shallow plugs.

The following was performed.

Plug No. 1 - Chase interval plugged by pumping 200 lbs. cottonseed hulls and 60 sacks 60/40 pozmix cement through tubing set on packer at 2494'. Tagged this plug at 2224 ft.

Retrieved 4 1/2" casing and packer to 1772 ft.  
Packer hung up. Cut 4 1/2" casing and left one joint of 4 1/2" casing at packer in hole.

Plug No. 2 - Circulated mud at 1525 ft. Spotted 50 sack 60/40 pozmix cement plug at 1525 ft. inside 7" casing.

Plug No. 3 - Set tubing at 700 ft. Pumped 135 sack cement plug, circulating cement to surface.

Plug No. 4 - Pumped 35 sacks of cement down 7" casing, circulating out of 10 3/4" surface casing.

RECEIVED

RECEIVED