

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kearny County. Sec. 34 Twp. 24S Rge. 38W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Surray Mid-Continent Oil Company
Lease Name Keith Dodge Well No. 1
Office Address 321 West Douglas - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 19 19 61
Application for plugging filed February 21 19 61
Application for plugging approved _____ 19 _____
Plugging commenced February 20 19 61
Plugging completed 8 PM - February 20 19 61
Reason for abandonment of well or producing formation Dry

NORTH

X			

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production None 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 5284 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Morrow</u>	<u>Dry</u>	<u>5084</u>	<u>5116</u>	<u>8-5/8"</u>	<u>2008</u>	<u>0</u>
<u>Mississippi</u>	<u>Dry</u>	<u>5178</u>	<u>TD</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hde with mud and placed 150 sack cement plug from 2650' to 2375'.
Placed 20 sack cement plug from 2030' to 1995' and 20 sack cement plug
from 670' to 600'. Ten sack cement plug placed from 35' to surface.

RECORDED
STATE CORPORATION COMMISSION

MAR 8 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Nash A. Gough (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nash A. Gough
321 West Douglas - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of March, 19 61

W. L. Lackamp
Notary Public.

My commission expires July 13, 1963

