


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kearney County, Sec. ³⁴ 35 Twp. 24 Rge. 38 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NW SE
Lease Owner Sooner Pipe & Supply Corporation
Lease Name Smalley "B" Well No. 1
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-3-66 19
Plugging completed 1-8-66 19
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 2670 Feet
Show depth and thickness of all water, oil and gas formations. PBTB 2560'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Herrington-Kricker		2456	2480	8 5/8"	649'	None
				5 1/2"	2666'	1461'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Pumped 20 sacks cement from 2560' to 2400'. Pulled 5 1/2" casing and dumped 25 sacks of cement from 700' to 600'. Mudded hole to 45' and ran 15 sacks of cement to cap well. Welded plate on surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Paul G. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Knight
(Address)

Subscribed AND SWORN to before me this 20th day of December, 1968
Margaret Melcher
Notary Public.



PR-9

FORMATION RECORD

15-093-00385-0000

Nature of Strata	Color	Top	Bottom	Straight Hole tests	Remarks
Sand		0	55		
Water gravel		55	95		
Sand		95	164		
Water gravel		164	205		
Blue Clay		205	465	400' 0°	
Sand + Clay		465	610		
Red Bed		610	657		Set 8 7/8" at 649'
" "		657	965	800' 0°	
Red Bed, gyps + salt		965	1574	1200' 0°	
Sand + shale		1574	1978	1600' 0°	
Anhydrite + shale		1978	2456	2000' 0°	
Merriam Dolomite		2456	2480	2400' 0°	
Shale		2480	2483		
Hicks Dolomite		2483	2488		
Shale		2488	2525		
Winfield Dolomite		2525	2543		
Shale		2543	2578		
Towanda Dolomite		2578	2593		
Shale		2593	2614		

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1965
CONSERVATION DIVISION
Wichita, Kansas

H. A. Smalley B # 1
Sec. 34-24-38"
NW NW SE Kearney Co KS.

