

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-093-20012-00-00

LEASE NAME Smalley

WELL NUMBER #1-34

1320 Ft. from S Section Line

1420 Ft. from E Section Line

SEC. 34 TWP. 24 RGE. 38 (E) or (W)

COUNTY Kearny

Date Well Completed 08/10/1968

Plugging Commenced 12/12/2002

Plugging Completed 12/12/2002

RECEIVED

12-23-02

TYPE OR PRINT

DEC 23 2002

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Geo. R. Shaw

ADDRESS 150 N. Main, Suite 1001 Wichita, Kansas 67202

PHONE (316) 267-0382 OPERATORS LICENSE NO. 5062

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/09/2002 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Chase Group Depth to Top 2396' Bottom 2471' T.D. 2471'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chase Group	Gas	2396'	2471'	10.750"	225'	none
				7.000"	2380'	none
				5.500"	104'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from 0 feet to 660 feet each set a bridge plug at 2295', spotted 2sx cement on plug, loaded the casing with fresh water, perforated the casing from 660'-661', pumped 17bbls of fresh water down the casing, pumped 225 sx of 60/40 Pozmix cement down the casing to circulate 25 sx of cement to the pit, cut off the casing 4' below ground level, and welded a steel plate on the casing strings.

Name of Plugging Contractor Halliburton Energy Services, Inc. License No. 5287

Address P.O. Box 1598 Liberal, Kansas 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Geo. R. Shaw

STATE OF Kansas COUNTY OF Finney, ss.

Ronald Osterbuhr

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) Ronald Osterbuhr

(Address) P.O. Box 1152 Garden City, KS 67846

SUBSCRIBED AND SWORN TO before me this 19th day of December, 2002

K. Renee Spillman

My Commission Expires: 2-21-03



OR