

15-009-03023-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1978  
6-26-78  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Roxana Corp.

Complete Address Box 611, Great Bend, Kansas 67530

Lease Name O'Leary Well No. 3

Location NE NW NE Sec. 8 Twp. 16 Rge. 11 (K) (W) X

County Barton Total Depth 3280'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas 67530 License No 670

Operation Completed: Hour 2:45 PM Day 23 Month 6 Year 1978

The above well was plugged as follows:

Sanded back to 2750' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 3 sx hulls,

25 sx mud gel, 1 sx hulls, plug, and 100 sx cement.

Max pres, 1000# Shut in pres 500#.

Plugged back to 3043' top perf. at 2794'.

Recovered 2400' of 4 1/2" casing

3278' of 4 1/2" casing cemented with 150 sx cement.

393' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 6-26-78

INV. NO. 7546-2