

DISTRICT CONSERVATION AGENT'S REPORT

R

15-009-06286-0000

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 43-5

LOCATION SW-SE-SE

SEC. 8 TWP. 16 RGE. 11W.

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 2 Lease New

Operator Petro. inc. Address R. 2 Great Bend Kansas

Field \_\_\_\_\_ County Barton

Total Depth 3315 Feet.

Plugging Contractor Morgan Well Plugging Service

Plugging Contractor's License No. 43

Address 102 W. 18th - Hutchinson Kansas  
(Describe Briefly the manner in which the well was plugged)

Sup. Pipe 8 3/4 @ 248 c.w.  
5 1/2 at 3301 sup. 50 sq. of cement + 25 v. strata crite  
sand to 3290 + 5 sq. of cement. Fall 5 1/2  
to 614 feet and circulate water soil out with  
well mud and fall 5 1/2 to 295 and pump in  
75 sq. of cement with Globe truck finish pulling  
5 1/2 and let set over night Check top of cement  
at 148 feet and mud

R. M. Brundage  
District Conservation Agent

Date Sept. 26 - 1957

~~and set~~  
and n.o. to 20 feet  
and 5 sq. of cement to  
the base of the collar at 10 feet

RECEIVED  
STATE CORPORATION COMMISSION

SEP 27 1957  
9-27-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 8 T. 16 R. 11W  
BOOK PAGE 42 LINE 5