

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CE 1/2 - NE - SW

SEC. 8 TWP. 16 RGE. 11 - W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mey

Operator Murphy Drilling Co Address 910 N. Main Bldg. Wichita - Kans
Field _____ County Barton

Total Depth 3342 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 286 ft. Circulated with cement.
5 1/2 casing set at 3334 ft. 100 sacks of cement - Filled
hole with sand to 3325 ft. Dumped 5 sacks of cement at 3325 ft.
Shot off & pulled the 5 1/2 casing - mud to 280 ft - Set
rock bridge & 20 sacks of cement at 280 ft. mud to 35 ft -
bridge & 10 sacks of cement at the surface -

RECEIVED
STATE CORPORATION COMMISSION District Conservation Agent

APR 2 - 1953 Date 3-28-53
4-2-53
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 16 R 11W
BOOK PAGE 89 LINE 21