

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Hitting Building
Wichita, Kansas

FILE NO. 76-3

LOCATION SW-SE-7E

SEC. 8 TWP. 16 RGE. 11-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Muller

Operator Hall Co - of Paducah, Ky. Address 826 N. 7th St. Wichita - Kansas

Field _____ County Barton

Total Depth 3339 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 238 ft. Circulated with cement.
5 1/2" casing set at 3330 ft - 150 sacks of cement.
Boher Plug at 3180 ft - cement to 3172 ft. Filled hole
with sand to 2840 ft - Drilled 5 sacks of cement at 2840 ft.
Shot 3/4" pulled the 6 1/2" casing - sand to 238 ft - Set
each bridge & 20 sacks of cement at 238 ft - sand to
35 ft - Plug & 10 sacks of cement at the surface
The West Supply Co. Plugging Contractor

PLUGGING
FILE SEC 8 T 16 R 11W
BOOK PAGE 76 LINE 3

RECEIVED
APR 15 1953
2-15-53
WICHITA, KANSAS

C. D. Stough
District Conservation Agent

Date 4-14-53