

15-009-20259-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Inc.

Complete Address 1515 Wichita Plaza, Wichita, Kansas 67202

Lease Name Houska Well No. # 1

Location NE NW SW Sec. 12 Twp. 16 Rge. 11 (E) W

County Barton Total Depth 3390

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Inc.

Address Box 364, Great Bend, Kansas 67530 License No. # 399

Operation Completed: Hour 1 P.M. Day 27 Month 6 Year 1969

The above well was plugged as follows:

8 5/8" 352' Cwc. 4 1/2" 3389' Perf. 3252'.

Set bottom plug @ 3200' & dumped 4 sax cement with dump bailer. Pulled pipe.

Mud to 340', set 20' rock bridge, & displaced 5 sax cement. Let set over night.

Bailed hole dry & displaced 4 yds. Ready-mix Cement, cementing from 300' to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don. Smead
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 12-W