

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

*W. Lewis Brock  
Admin. Building  
Wichita, Kansas*

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Graves Drlg. Co. Inc.

Complete Address 505 Union Center Wichita, Ks

Lease Name Parkin Well No. 1

Location C SE/SW Sec. 8 Twp. 30 Rge. 18 (E) W

County Kiowa Total Depth 5100

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 5:00 PM Day 7 Month 6 Year 1971

The above well was plugged as follows:

531 ft 8 5/8 surface pipe cemented, circulated. 5064 ft 5 1/2 long string  
cemented with 100 sacks. Top perf. 4997 ft. Sand back to 4980 ft,  
5 sacks cement with bailer. Pulled 3585 ft 5 1/2. Set 10 ft rock bridge  
at 300 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. Russell Biker*  
Well Plugging Supervisor

INVOICED

DATE 6-9-71

INV. NO. 3875-W