

CP3

15-009-06347-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 26-7

LOCATION SW-NW-NE

SEC. 7 TWP. 16 RGE. 11-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Esfeld

Operator E. Heredo Refining Co Address Box 209 - Russell, Kans.

Field _____ County Barton

Total Depth 3316 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 300ft. Circulated with cement
5 1/2" casing set at 2938ft. Cemented with 60 sacks cement -
Lower Wells Plug at 2850ft. Plugged back to 2820ft.
with sand - Dumped 4 sacks of cement at 2820ft =
Shot off & pulled the 5 1/2" casing. Filled with mud to
300ft. Set Rock Bridge & 15 sacks of cement at 300ft =
Mud to 30ft. Plug & 10 sacks of cement
at the surface. Shall be pulled by contractor.

RECEIVED
Conservation Div.

SEP 18 1950
9-18-50
STATE CORPORATION
COMMISSION

W. H. Stough
District Conservation Agent

Date 9-15-50

PLUGGING
FILE SEC 7 T 16 R 11W
BOOK PAGE 26 LINE 7