

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. SE SW SE

LOCATION SE 1/4

SEC. 7 TWP. 16 RGE. 11-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Standing

Operator Thos. B. Oil Co. Address Box #4671 Okla City-9 - Okla.

Field \_\_\_\_\_ County Butler

Total Depth 3263 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 212 ft. Circulated with cement.  
5 1/2 casing set at 3265 ft - 75 sacks of cement.  
Repacked 5 sacks of cement on bottom of hole.  
Shot off & pulled the 5 1/2 casing - mud to 212 ft.  
Set rock bridge & 10 sacks of cement at 212 ft.  
Mud to 355 ft - Bridge & 10 sacks of  
cement at the surface.

**PLUGGING**  
FILE SEC 7 T 16 R 1 W 4-10-52  
BOOK PAGE 7 LINE 39  
1952

C. D. Stovish  
District Conservation Agent  
Date 4-8-52