

15-009 20256-0000
Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1968
CONSERVATION DIVISION
Wichita, Kansas
8-19-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Schreiner Petroleum

Complete Address: 207 Petroleum Bldg. Wichita, Kansas

Lease Name Esfeld Well No. 2

Location SE NW ^{NE} ~~SE~~ Sec. 7 Twp. 16 Rge. 11 (E) (W) X

County Barton Total Depth 3319

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: B - B Drlg.

Address: Wichita, Kansas License No. 598

Operation Completed: Hour 9:15 P Day 16 Month 8 Year 1968

The Above well was plugged as follows:

RTD 3319' 8 5/8 csg set at 249' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 400' and displaced 30 sc cmt. thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 8/19/68
INV. NO. 8300-u