

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1978
4-12-78
CONSERVATION DIV. S.O.
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009-20945-0000 (of this well)

Operator's Full Name Lario Oil & Gas Co.

Complete Address 301 South Market, Wichita, Kansas 67202

Lease Name Esfeld Well No. 3

Location NW NW Sec. 7 Twp. 16 Rge. 11 ~~000~~ (W) X

County Barton Total Depth 3328'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chaspe, Kansas 67524 License No. 683

Operation Completed: Hour 9:00 AM Day 10 Month 4 Year 1978

The above well was plugged as follows:

- Sanded Back to 2900' and 5 sx cement with dump bailer.
- Mud to 420', rock bridge from 420' to 400' & 6 yds. ready
- mix cement to bottom of cellar. Plugged back to 3020'.
- Recovered 2608' of 5 1/2" casing. Top perf. at 2956'.
- 3328' of 5 1/2" casing cemented with 125 sx cement.
- 786' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-12-78
INV. NO: 7099-W

Signed: Duane Rankin
Well Plugging Supervisor