


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:

Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 11 Twp. 16 S Rge. 11 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW
Lease Owner C. E. Ash ET AL
Lease Name Montgomery Well No. 1
Office Address 309 Ellis Singleton Bldg.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry
Date, well completed Dec. 6, 1939 193
Application for plugging filed Dec. 6, 1939 193
Application for plugging approved Dec. 7, 1939 193
Plugging Commenced Dec. 7, 1939 193
Plugging Completed Dec. 13, 1939 193
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Depth to top Bottom Total Depth of Well 3422 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	H.F. Water	235	250	15 1/2	430	430
Sandy Lime	1 B. Water	1745	1750	12 1/2	705	705
Lime	1 1/2 B. Water	2692	2705	10	1978	1978
Lime	Show oil	3075		8 5/8	2380	2380
Lime	3/4 B. Water	3100		7	3345	3345
Lime	Show Gas	3280				
Lime	H.F. Water	3393	3399			
Lime	Show oil	3399	3401			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded from 3422 to 3390

Cemented from 3390 to 3375

Mudded from 3375 to 3030

Cemented from 3030 to 3015

Filled with mud 3015 to 290


Cemented from 290 to 270

Mudded from 270 to bottom of cellar

Cemented bottom of cellar and filled with dirt to surface

Cement was placed with cement dump bailer

Mud was placed in hole with slip



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C. E. Ash
Address 309 Ellis Singleton Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. E. Ash (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

309 Ellis Singleton Building
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of December, 1939

My commission expires April 15, 1942.

17-6058

10-88-5M

12-16-39
J. L. House
DEC 13 1939
STATE Notary Public
Wichita, Kansas

Comm. Rig Up: 10/9/39
Comm. Drlg. : 10/12/39
Completed : 12/12/39
Total Depth : 3422
Elevation :
Initial Prod: D & A

C. E. ASH ET AL
Montgomery No. 1
NW NW of Sec. 11,
Township 16 South,
Range 11 West,
Barton County, Kansas

CASING RECORD

Run		Pulled	Left In
15 1/2"	430'	430'	
12 3/8"	705	705	
10"	1978	1978	
8 5/8"	2380	2380	
7"	3345	3345	

STRATA	DEPTH
Yellow Rock	15
Lime	25
Blue Slate	40
Shale	145
Lime	152
Blue Slate	180
Shale	195
Red Rock	210
Shale	235
Water Sand	270
HFW 235-250	
Light Shale	430
Blue Shale	450
Dark Sand	470
Shale	475
Blue Slate	505
Red Rock	530
Blue Shale	568
Red Rock	600
Lime	603
Red Rock	697
Anhydrate Lime	724
Red Rock	915
Blue Shale	975
Red Rock	1030
Blue Shale	1140
Salt	1387
Shale	1395
Lime	1405
Light Shale	1412
Lime	1450
Shale	1460
Lime	1475
Red Rock	1479
Lime	1507
Red Rock	1515
Blue Shale	1525
Lime	1560
Shale	1568
Lime	1610
Shale	1615
Red Rock	1625
Lime	1670
Red Rock	1674
Lime	1745
Sandy Lime	1773
1 BW 1745-1750	
Red Rock	1785
Lime	1795
Shale	1830
Lime	1840
Shale	1845
Lime	1855
Red Rock (Cave)	1870
Lime	1905
Red Rock	1910
Lime	1940

STRATA	DEPTH
Red Rock	1948
Lime	1970
Red Rock	1975
Lime	1988
Red Rock	2000
Lime	2068
Shale	2073
Lime	2100
Shale	2108
Lime	2140
Shale	2155
Lime	2160
Shale	2192
Broken Lime	2204
Shale	2260
Lime	2273
Red Rock	2278
Shale	2290
Lime	2297
Shale	2327
Lime	2335
Shale	2375
Lime	2393
Shale	2443
Lime	2462
Shale	2467
Lime	2473
Shale	2478
Lime	2483
Shale	2492
Lime	2502
Shale	2508
Lime	2535
Shale	2580
Lime	2612
Shale	2623
Lime	2753
1 1/2 BW 2692-2705	
Shale	2756
Lime	2773
Shale (Cave)	2778
Lime	2923
Shale	2930
Lime	2953
Red Rock (Cave)	2958
Lime	2960
Blue Shale	3006
Lime	3015
Shale	3020
Lime	3022
Red Rock	3029
K. C. Lime	3117
3/4 BW 3100	
Shale	3120
Lime	3145
Shale	3150
Lime	3160

STRATA	DEPTH
Shale	3167
Lime	3230
Shale	3235
Lime	3268
Shale	3273
Lime	3293
Show Gas 3280	
Shale	3298
Lime	3308
V. C. Shale	3316
Black Shale	3320
V. C. Shale	3325
Red Rock	3327
Lime	3335
Red Rock	3345
Cherty Lime	3386
Sil Lime	3422
HFW 3393-3399	
Show Oil 3399-3401	
Total Depth	3422

This is a true and complete copy of the log of the above well, as kept by me.

C. E. Ash
.....
C. E. Ash

Subscribed and sworn to
December 12th, 1939.

Julia House
.....
Notary Public

My commission expires
April 15, 1942.

