


15-009-21171-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 12 Twp. 16S Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C N/2 NE/4
Lease Owner Frank Kennec
Lease Name Horejsi Well No. 1-A
Office Address Box 419, Wilson, KS 67490
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 6-9 1977
Application for plugging filed 6-9 1977
Application for plugging approved 6-9 1977
Plugging commenced 6-9 1977
Plugging completed 6-9 1977
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3433
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	304'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud laden fluid	3433 to 500'
40 sks cement @	500'
20 sks cement @	300'
Plug, 1/2 sk. hulls & 10 sks cement @ 40'	
2 sks cement in rat hole	

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1977
06-16-77
COMMUNICATIONS SECTION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations
Box 506, Russell, KS 67665


STATE OF KANSAS COUNTY OF RUSSELL, ss.
Joe K. Branum (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
Box 506, Russell, KS 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1977

Patricia L. Clark
Notary Public.

My commission expires October 2, 1979



EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: Frank Kennec
Box 419
Wilson, Kansas 67490

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, Kansas 67665

LEASE: Horejsi WELL: #1-A

LOCATION: C N/2 NE/4
Section 12-16S-11W
Barton County, Kansas

Total Depth: 3433'
Commenced: 6-2-77
Casing: 8-5/8" @ 304'

Elevation:
Completed: 6-9-77
Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Shale & Rock	340	Shale	1967
Shale & Sand	700	Lime & Shale	3224
Anhydrite	745	Lime	3246
Shale	1066	Lime & Shale	3400
Shale & Shells	1585	Lime (R.T.D.)	3433

JUN 16 1977
NOTARY PUBLIC

STATE OF KANSAS)
COUNTY OF RUSSELL) SS

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned location.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 13th day of June, 1977.
My Commission Expires: October 2, 1979.

Patricia L. Clark

Notary Public

