


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 7 Twp. 16S Rge. 11 XX (W)

Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner Francis Oil & Gas, Inc.
Lease Name Esfeld Well No. 1
Office Address 905 Palace Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 23, 1964
Application for plugging filed January 23, 1964
Application for plugging approved January 23, 1964
Plugging commenced January 23, 1964
Plugging completed January 23, 1964
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,260' (RTD) to 240'. Set bottom plug at 240' and cemented with 25 sacks cement and 1/4 sack hulls. Filled hole with heavy rotary mud to 40'. Set top plug at 40' and cemented with 15 sacks cement and 1/4 sack hulls.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1964
1-30-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. contractor
Merle Britting (employee of ~~owner~~ or ~~owner of operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 64

My commission expires December 3, 1964.
Geraldine Hays Notary Public.



KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-009-06252-0000


COMPANY **Francis Oil & Gas, Inc.**
 FARM **Esfeld** NO. **1**

SEC. **7** 16S 11W
 SW SE NE
 LOC.

TOTAL DEPTH **3,260'**
 COMM. **1-15-64** COMP. **1-23-64**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Barton**

KANSAS



CASING
 20 10 5/8" 244' cem w/165 sz
 15 8
 12 6
 13 5

ELEVATION **1809 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	15
Post Rock	50
Rock & Shale	244
Shale, sand & red bed	665
Anhydrite	695
Shale & Shells	1450
Shale & Lime	1550
Lime & Shale	2110
Shale & Lime	2578
Lime & Shale	3249
Conglomerate	3260
Rotary Total Depth	3260

Sample Tops

Anhydrite Top	665	+1144
Anhydrite Base	695	+1114
Topeka	2562	- 753
Heebner	2847	-1038
Toronto	2867	-1058
Douglas	2879	-1070
Br. Lime	2942	-1133
Lansing	2955	-1146
Base K. C.	3226	-1417
Conglomerate	3245	-1436
Rotary T. D.	3260	-1451

RECEIVED
 STATE CORPORATION COMMISSION

JAN 30 1964

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Merle Britting

STATE OF KANSAS }
 SELGWICK COUNTY } SS.

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 29th day of January, 1964.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:
 December 3, 1964.