


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines Barton County. Sec. 7 Twp. 16S Rge. 11 XW (W)
 Lease Owner Herman Geo. Kaiser
 Lease Name Staudinger Well No. 1
 Office Address 909 Palace Building, Tulsa, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed June 1, 19 63
 Application for plugging filed June 1, 19 63
 Application for plugging approved June 1, 19 63
 Plugging commenced June 1, 19 63
 Plugging completed June 1, 19 63
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,320 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 300 feet. Set bottom plug at 300 feet and cemented with 1/4 sack hulls and 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40 feet and cemented with 1/2 sack hulls and 10 sacks cement, filling hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1963
6-5-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
 Address 200 North Main, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. contractor
Priscilla M. Ismert (employee of owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Priscilla M. Ismert
200 North Main, Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 4th day of June, 19 63

Geraldine Hays
 Geraldine Hays Notary Public.

My commission expires December 3, 1964.



KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


15-009-06253-0000

COMPANY **Herman Geo. Kaiser**
 FARM **Staudinger** NO. **1**

7 168 11W
 SEC. S/2 NE SW.
 LOC.

TOTAL DEPTH **3,320'**
 COMM. **5-24-63** COMP. **6-1-63**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Barton**



CASING
 20 **1 5/8" 305' cen. w/175 sz**
 15 **B**
 12 **6**
 13 **5**

1862 GR
 1864 DR
 ELEVATION 1867 MB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock	75
Sand, Shale & Shells	280
Shale & Shells	305
Shale	325
Sand	455
Red Bed & Shale	730
Anhydrite	758
Shale & Shells	1440
Line & Shale	2010
Shale & Lime	2180
Shale & Shells	2360
Shale & Lime	2687
Line & Shale	3030
K. C. Line	3075
Line	3202
K. C. Line	3250
Line	3320
Rotary Total Depth	3320

RECEIVED
 STATE CORPORATION COMMISSION

JUN 5 1963

CONSERVATION DIVISION
 Wichita, Kansas

Sample Tops

Anhydrite Top	730	/1137
Anhydrite Base	758	/1109
Topoka	2626	- 759
Reebner	2915	-1048
Toronto	2935	-1068
Douglas	2945	-1078
Br. Line	3008	-1141
Lansing	3024	-1157
Base K. C.	3268	-1421
Conglomerate	3311	-1444
Rotary T.D.	3320	-1453

I hereby certify that the above and foregoing is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *Priscilla M. Lambert*
 Priscilla M. Lambert

STATE OF KANSAS }
 SEDGWICK COUNTY } SS:

Subscribed and sworn to before me, a notary public in and for said county and state, this 4th day of June, 1963.

Geraldine Hays
 Geraldine Hays, Notary Public.

My Commission Expires:
 December 3, 1964.