

15-009-06 2850000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

Barton

County. Sec. 7 Twp. 16 Rge. 11 (E) W. (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE NW

Lease Owner V. E. Autry

Lease Name E. Woydziak Well No. 1.

Office Address 1007 Gulf States Building, Dallas, Texas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 24, 19 54

Application for plugging filed March 24, 19 54

Application for plugging approved March 24, 19 54

Plugging commenced March 24, 19 54

Plugging completed March 24, 19 54

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud from bottom to 230'. 20 sacks cement at 230'  
Filled with heavy rotary mud to 25'. 10 sacks cement filled hole from 25' to surface.

STATE OF KANSAS  
CONSERVATION DIVISION  
WICHITA, KANSAS  
4-1-54

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to V. E. Autry,  
Address 1007 Gulf States Building, Dallas, Texas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

H. M. Williams (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. M. Williams  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 54

My commission expires Feb. 2, 1957.

23-5091-s 8-50-10M

PLUGGING  
FILE SEC 27 16 11W  
BOOK PAGE 23 LINE 1

R. P. Larson  
Notary Public.

WELL LOG.

V. E. Autry  
 E. Woydziak Well No. 1.  
 Total Depth 3350'  
 Drilling Comm. Mar. 15, 1954  
 Drilling Comp. Mar. 24, 1954  
 Drilling Contractor, H. M. Williams

Sec 7 T. 16S R. 11W  
 SW SE NW  
 Barton County, Kansas.  
 Casing:  
 8 5/8" 234' 225 Sks Cement  
 Production. Dry.  
 Elevation 1840' DF 1837 Gr.  
 Production. Dry.

Figures indicate bottom of formations.

Shale Shells	55		
Sand	70		
Shale & Shells	900		
Shells	960		
Red Bed Salt	1300		
Shale & Shells	1525		
Lime & Shale	1825		
Lime	2055		
Lime & Shale	2155		
Shale	2415		
Shale, Shells & Lime	2565	Top Heebner	2888
Shale & Lime	3015	Top Toronto	2906
Lime	3181	Top Douglas	2920
Lime & Shale	3285	Top Brown Lime	2980
Lime	3330	Top Lansing	2998
Conglomerate	3350	Top Cong.	3285
Rotary Total Depth.	3350		

RECORDED  
 STATE CORPORATION  
 APR 1 1954  
 4-1-1954  
 COMMISSIONER OF MINES AND GEOLOGY  
 DIVISION  
 KANSAS

**PLUGGING**  
 FILE SEC 7 T 16 R 11W  
 BOOK PAGE 23 LINE 1