

WELL PLUGGING RECORD

15-009-07186-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County, Sec. 7 Twp. 16S Rge. 11W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SE

Lease Owner Three "B" Oil Company

Lease Name Staudinger Well No. 2

Office Address Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Abandoned Oil Well

Date well completed 19

Application for plugging filed December 1, 1951 19

Application for plugging approved April 10, 1952 19

Plugging commenced 4-4-52 19

Plugging completed 4-8-52 19

Reason for abandonment of well or producing formation oil depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

C. D. Stough

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	212'	None
				5-1/2"	3260'	1639'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3263' to 3236' and ran 5 sacks of cement. Mudded hole from 3186' to 275', set 101 rock bridge and ran 25 sacks of cement. Mudded hole to 25', set rock bridge and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Willie Bendorf (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Willie Bendorf

(Address)

SUBSCRIBED AND SWORN to before me this 19th day of April, 1952

Louis Bendorf Notary Public.

My commission expires Jan. 16, 1955

23-8390-s 6-51-20M

PLUGGING
FILE SEC 7 T 16 R 11C
BOOK PAGE 7 LINE 39

APR 21 1952

4-21-52

Wichita, Kansas

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


15-009-67186000

GULF OIL CORP.
V. Staudinger No. 2.

SEC. 7 T. 16 R. 11 W
SE SW SE
1020' f WL 330' f SL SE $\frac{1}{4}$

Total Depth. 3263'
Comm. 2-8-43 Comp. 3-4-43
Shot or Treated. 3-4-43 1000 Gals. Acid
Contractor,
Issued. 4-24-43

County. Barton



CASING:
8 5/8" 212' Cem. LI
5 1/2" 3260' Cem. LI

Elevation.

Production. Pot. 112 B.
No wtr

Figures Indicate Bottom of Formations.

sand, gravel, shale	0-212
red bed & shale	645
shale & shells	955
anhydrite	975
shale & shells	1080
shale & salt	1335
shale & shells	1460
shale & lime	1695
lime sdy	1725
lime	1825
lime & shale	2010
shale & shells	2560
lime	3259
Arbuckle lime	3263
Total Depth.	

Top Lansing 2980
Arbuckle lime 3259-63

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 16 R 11 W
BOOK PAGE 7 LINE 39