

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24519-6000

LEASE NAME Schremmer

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

3530 Ft. from E Section Line

SEC. 7 TWP. 16 SRGE. 11 (X) or (W)

COUNTY Barton

LEASE OPERATOR HAR-KEN Oil Company

ADDRESS 2932 NW 122, Unit 15 Oklahoma City, OK 73120

PHONE# (405) 752-0318 OPERATORS LICENSE NO. 9911

Date Well Completed 8-06-92

Character of Well D&A

Plugging Commenced 8-06-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-06-92

The plugging proposal was approved on August 6, 1992 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3375

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	380'	8 5/8"	380'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

25 sx. @ 3280', 25 sx. @ 750', 100 sx. @ 480', 10 sx. @ 40', 15 sx. in rathole.
Total: 175 sx. 60/40 Pozmix, 6% Gel W/1# flo seal per sk. Halliburton

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. RECEIVED

Address R.R. 1 Box 183 B Great Bend, Ks. 67530 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HAR-KEN Oil Company AUG 12 1992

STATE OF KANSAS COUNTY OF BARTON, ss. CONSERVATION DIVISION
Wichita, Kansas

L. D. Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) L. D. Davis

(Address) L. D. Davis
R.R. 1 Box 183 B Great Bend, KS.
67530

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 92

Bessie M. DeWerff
Notary Public

My Commission Expires: 5-20-93 Bessie M. DeWerff



DRILLER'S WELL LOG

15009-24519-0000

COMMENCED: 7-31-92
COMPLETED: 8-06-92

0 - 330 Rock
330 - 750 Red Bed
750 - 2655 Lime & Shale
2655 - 2855 Lime
2855 - 3270 Lime & Shale
3270 - 3312 Lime & Cong.
3312 - 3375 Lime
3375 RTD

HAR-KEN Oil Company
SCHREMMER #1
SW NE NW Sec. 7-16S-11W
Barton County, Kansas

ELEVATION: 1870' GL 1875' KB

FORMATION DATA: (sample)

Anhydrite 738-63 (+1138)
Heebner 2916 (-1041)
Brown Lime 3005 (-1130)
Lansing 3022 (-1147)
Base K/C 3234 (-1359)
T/Congl 3300 (-1425)
Arbuckle 3322 (-1447)
RTD 3375 (-1500)

SURFACE CASING:

8 5/8" set @ 380' W/170 sx.
60/40 Pozmix, 2% Gel, 3% CC

A F F I D A V I T


STATE OF KANSAS)
) ss
COUNTY OF BARTON)

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


L. D. Davis

Subscribed and sworn to before me this 11th day of August, 1992.

My Commission expires: 5-20-93


Notary Public: Bessie M. DeWerff

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1992
CONSERVATION DIVISION
Wichita, Kansas