

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

15-009-30275-0000

Barton County, Sec. 7 Twp. 16 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines N 1/2 NW SW
Lease Owner Aylward Drilling Company
Lease Name Staudinger Well No. 1
Office Address 909 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 7, 1965
Application for plugging filed April 7, 1965
Application for plugging approved April 7, 1965
Plugging commenced April 7, 1965
Plugging completed April 7, 1965
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3330 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up to 310 feet, set plug with 1/4 sack hulls and 25 sacks cement through drill pipe. Mud up to 40 feet. Set plug with 1/2 sack hulls and 15 sacks cement. Bridged rathole and cemented with 5 sacks.

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1965
4-21-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Frank Hamlin (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
909 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of April, 1965

My commission expires May 14, 1968

Joseph A. Hess
JOSEPH A. HESS Notary Public.



15-209-30275-0000

STAUDINGER #1

Casing Record: Company: Aylward Drilling Company Location: N $\frac{1}{2}$ NW SW 7-16-11W
 Contractor: Aylward Drilling Company Barton County, Kansas
 8 5/8" - 320'
 Commenced: March 29, 1965 Elevation: 1866 K.B.
 Completed: April 7, 1965

	<u>From</u>	<u>To</u>	<u>Remarks</u>	
Soil	0	5	Set 8 5/8" surface pipe @ 320' w/185 sacks cement.	
Post Rock	5	55		
Shale & Lime Streaks	55	85	Geological Tops:	
Gumbo Shale	85	100		
Shale	100	730		
Anhydrite	730	763		Topeka 2630
Shale	763	1125		Heebner 2916
Shale w/Lime Streaks	1125	1442		Toronto 2936
Shale & Lime	1442	1631		Douglas 2949
Shale	1631	1810		Brown Lime 3010
Shale & Lime	1810	1860		Lansing 3024
Shale w/lime Streaks	1860	2025		Arbuckle 3320
Shale & Lime	2025	2215		
Lime & Shale	2215	2421		DST 2860-90 Open 1 hr.
Shale w/Lime Streaks	2421	2608		Rec. 60' watery mud
Shale & Lime	2608	2805		IBHP 1027#/30" - FBHP 858#/30"
Lime w/Shale Streaks	2805	2890		FP 38-45#
Lime	2890	2950		
Shale	2950	3010		DST 3026-60 Open 1 hr.
Lime	3010	3015	Rec. 240' gas in pipe plus 60'	
Shale	3015	3025	GCM w/sl. show oil	
Lime	3025	3060	IBHP 198#/30" - FBHP 91#/30"	
Lime & Shale Streaks	3060	3130	FP 45-45#	
Lime	3130	3330 T.D.		
			D & A	
			DST 3280-3330 Open 1 hr.	
			Rec. 25' mud & 5' oil	
			IBHP 950#/30" - FBHP 651#/30"	
			FP 38-38#	

RECEIVED
 STATE CORPORATION COMMISSION

APR 21 1965

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Frank Hamlin

Subscribed and sworn to before me this 9th day of April, 1965

Joseph A. Hess
 JOSEPH A. HESS Notary Public

My commission expires May 14, 1968