

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-095-00002-0000
API NUMBER N/A

LEASE NAME Messenger A

WELL NUMBER #1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 31 TWP. 30S RGE. 8 ~~W~~ (W)

COUNTY Kingman

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS 110 N. Market, Suite #205; Wichita, KS 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/28/89 (date)

by John Sanders, Warren Kirkpatrick (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4318 Bottom T.D. T.D. 4428

Perfs = 4360'-4370' & 4380'-4390'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	160	8 5/8"	160	None
Mississippi	Oil, gas, water	-0-	4423	4 1/2"	4423	Top 1134 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CTBP @ 4260', 10 sx 60/40 poz @ 1370', 35 sx 60/40 poz @ 1175', 35 sx 60/40 poz @ 800', 90 sx 60/40 poz, Circ. from 300' to surface. Top plug leaked. After 14 days drilled out top plug to 185' and plugged w/10 bbls. mud, 50 sx common, plug, 35 sx common, plug, 15 sx common. Held O.K.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A

Address Box 31, Russell, KS 67068

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack Gurley, Engineer

(Address) 110 N. Market, #210; Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 89

Susan Kendall
Notary Public

My Commission Expires: 10/6/91 Susan Kendall

KCC OIL/GAS REGULATORY OFFICE

15-095-00002-0000

DATE 5-15-89

- New Situation
- Response to Request
- Follow-up

OPERATOR Pickrell Drly Co. #5123

NAME 110 N. Market #205

LOCATION NE/4W/SE, SEC 31, T 30S, R 8 ^E

ADDRESS Wichita KS 67202

LEASE Messenger Well # A-1

PHONE NO. OPER. 316-262-8427 OTHER

COUNTY Kingman

REASON FOR INVESTIGATION: Poor Plug job

LEASE INSPECTION

PROBLEM: Gas coming up thru cement.

PERSON(S) CONTACTED: Don Amiller - Pickrell Drly.

FINDINGS: The cement was drilled out from 0-300' which was the top plug.

COMPLAINT

The hole was then squeeze plugged thru the 8 1/2" surface pipe by pumping 10 bbls of drilling mud, 50 sks of cement, a wiper plug, 35 sks of cement, a wiper plug, and 15 sks of cement.

Allied Cementing Co. ticket # 1222
100 sks of Common Cement.

RECEIVED
STATE COMPLETION COMMISSION
MAY 18 1989

ACTION/RECOMMENDATIONS: None

Replug - do not kill

FIELD REPORT

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Steve Anderson
5-16-89

CC: Marguerite

WK