


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kingman County, Sec. 30 Twp. 38 Rge. (E) 8 (W)  
Location as "NE, CNW, SW" or footage from lines NE-NE NW  
Lease Owner Pickrell Drilling Company  
Lease Name Richardson "B" Well No. 1  
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 8, 1957  
Application for plugging filed August 8, 1957  
Application for plugging approved August 8, 1957  
Plugging commenced August 8, 1957  
Plugging completed August 8, 1957  
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 4376 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 250', bridge hole and cemented with 20 sacks cement. Then heavy mud to 35' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
G. W. Sebitt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
705 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of August, 1957

My commission expires July 30, 1958

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC. 30 T. 30 R. 8W  
BOOK PAGE 35 LINE 15

AUG 23 1957  
8-23-57  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company  
Wichita, Kansas

Rotary Drilling Commenced 7/26/57  
Rotary Drilling Completed 8/8/57

LOCATION: NE NE NW, Sec. 30-30S-8W, Kingman County, Kansas

CONTRACTOR: Richardson B-1  
PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 240' (6 jts.) 8 5/8" Armco Spiralweld Casing cemented with 200 sacks cement circulated.

Filled with heavy mud to 250', bridge hole and cemented with 20 sacks cement. Then heavy mud to 35' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand & Clay	75
Red Rock	360
Shale & Shell	875
Salt, Shale & Shells	1145
Lime & Shale	1760
Lime	2150
Lime & Shale	2360
Shale	2450
Shale & Shells	2640
Lime & Shale	3327
Lime, Shale & Sand	3616
Lime	4115
Lime & Shale	4285
Mississippi	4315
Lime	4376 T.D.

Circ. for samples at 4024'  
4295'  
4305'  
4376'

S.L.M. 2000 - O.K.  
3000 - "  
4000 - "

Slope Test 2000 - 0° off  
3000 - 0° off  
4000 - 0° off

PLUGGING  
FILE SEC. 30, T. 30, R. 8W  
BOOK PAGE 35, LINE 15

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
Attorney-in-Fact  
RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS, }  
COUNTY OF SEDGWICK } ss.

On this 22nd day of August, 19 57, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

[Signature]  
Notary Public