

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 29 Twp. 30S Rge. 8W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW NE

Lease Owner National Cooperative Refinery Association - Beardmore

Lease Name Carrick Unit Well No. 1

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 27, 1959

Application for plugging filed May 27, 1959

Application for plugging approved May 28, 1959

Plugging commenced May 27, 1959

Plugging completed May 27, 1959

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4701 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	251'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Conditioned hole and mudded to 240'. Set 18 sacks cement plug at 240'. Mudded to 35'. Set 10 sacks cement plug at 35'. Filled on up to base of cellar.

RECEIVED
CORPORATION COMMISSION
JUL 9 1959
7-9-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address 827 Beacon Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

C. R. Sears (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears. (C. R. Sears)

305 Rule Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1959

My commission expires November 26, 1960

Nell McComb Notary Public.

PLUGGING
FILE SEC. 29 T. 30 R. 8W
BOOK PAGE 40 LINE 34

Beardmore & N. C. R. A.
Carrick Unit #1
C NW SW NE Sec. 29-30S-8W
Kingman County, Kansas.

Drilled by: Beardmore Drilling Co.
Drilling Commenced: 5-14-59
Drilling Completed: 5-27-59

Casing Record:

Ran 253' of 8 5/8" surface pipe set at 251' with 175 sacks common cement.

Elevations: KB 1637'
DF 1634'
GR 1631'

<u>FORMATIONS</u>	<u>DEPTH</u>
Cellar	5
Sand	100
Red Bed & shells	500
Red Bed	740
Anhydrite	770
Shale	1185
Shale & lime	2450
Shale w/lime streaks	2680
Shale & lime	3370
Sand	3452
Shale & sand	3474
Sand	3543
Lime & shale	3575
Lime	3750
Lime & shale	3815
Lime	4016
Lime & shale	4095
Lime	4160
Lime & shale	4210
Lime	4260
Lime & shale	4307
Miss. Lime	4335
Lime	4472
Lime & Chert	4505
Lime	4535
Lime & shale	4627
Viola lime	4675
Sand	4700
Simpson Sand	4705
Rotary Total Depth	

WELEX TOPS:

Heebner	3324
Toronto	3339
Douglas	3356
Kansas City	3548
Base/Kansas City	4060
Mississippi	4298
Kinderhook	4515
Viola	4624
Simpson	4673
Total Depth	4701

STATE OF KANSAS }
COUNTY OF SEDGWICK)

PLUGGING	
FILE	SEC. 29 T. 30 R. 8W
BOOK	PAGE 40 LINE 24

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

John Beardmore

Subscribed and sworn to before me this 2nd. day of June, 1959.

Leonard P. Tolle

Leonard P. Tolle - Notary Public