

15-009-06289-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 17 Twp. 16 Rge. 11 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NE NW NE
Lease Owner National Cooperative Refinery Association
Lease Name Ney Well No. 4
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31, 1957
Application for plugging filed September 3, 1957
Application for plugging approved September 3, 1957
Plugging commenced August 31, 1957
Plugging completed August 31, 1957
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3359 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					8 5/8"	256'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole to 300'. Set plug / 75 sacks of cement through drill pipe. Mudded hole to 45', set plug (1/3 sack hulls) / 15 sacks of cement on up to base of cellar. Completed at 6:00 a.m. on August 31, 1957. R. M. Brundege, State Plugging Supervisor.

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1957
9-18-57

CONSERVATION DIVISION
(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address 311 East Third Street, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1957

My commission expires November 26, 1960.

Nell McComb
Nell McComb Notary Public.

PLUGGING
FILE SEC. 17 T. 16 R. 11 W
BOOK PAGE 41 LINE 45

WELL LOG

15-009-06289-0000

COMPANY NATIONAL COOPERATIVE REFINERY ASSN.

SEC. 17 T. 16S R. 11W

FARM NEY NO. 4


LOC. NE, NW, NE

TOTAL DEPTH 3359'

COUNTY Barton Co., Kansas

COMM. August 22, 1957 m COMP. August 31, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 256' W/150 sax.

ELEVATION 1847' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50	Postrock
160	Shale & sand
256	Shale & shells
675	Red bed, shale & shells
705	Shale
747	Anhydrite
1480	Shale & shells
2950	Lime & shale
3359	Lime
3359	T. D.

PLUGGING
 FILE SEC. 17 T. 16 R. 11W
 BOOK PAGE 41 LINE 45

RECEIVED
 STATE CORPORATION COMMISSION

SEP 18 1957

REGISTRATION DIVISION
 State of Kansas

Garvey Drilling Co.

State of KANSAS }
 County of BARTON } ss:

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #4 Ney well

Verne A. Morris

Subscribed and sworn to before me this 10th day of September 19 57

My Commission Expires November 12, 1958

Beaufort
 NOTARY PUBLIC