

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Barton County. Sec. 17 Twp. 16 Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines NW SE SE
Lease Owner Graham-Messman-Rinehart Oil Company
Lease Name Oeser Well No. 2
Office Address P. O. Box 1033
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed July 15 19 51
Application for plugging filed September 27 19 52
Application for plugging approved September 27 19 52
Plugging commenced September 28 19 52
Plugging completed September 28 19 52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough, Box 207, Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	560'	None
				5 1/2"	3350'	1600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill up with sand to 2900'. Dump 5 sx. cement.
Shoot off pipe at 1600' to pull. Mud to 300'.
Bridge and dump 20 sx. cement. Mud to 35' and
dump 10 sx. cement.

RECEIVED
OCT - 6 - 52
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Messman-Rinehart Oil Company
Address P. O. Box 1033, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me and.
(Signature) [Signature]
P. O. Box 1033, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October 19 52
Olive Carter
Notary Public.

My commission expires March 21, 1955

PLUGGING
FILE SEC 17 T 16 R 11
BOOK PAGE 48 LINE 17

15-009-066-25000

DRILLERS LOG

OESER #2

Casing Record:
8 5/8" - 560' with 250 sx. cement
5 1/2" - 3350' with 90 ~~sx~~ sx. cement

Company: Graham-Messman-Rinehart Oil Co.
Contractor: G-M-R
Description: NW SE SE 17-16-11W, Barton Co.
Commenced: July 5, 1951
Completed: July 15, 1951

<u>Formation</u>	<u>From</u>	<u>To</u>	
Native Stone & Shale	0	40	
Shale & Shells	40	360	
Shale & Sand	360	470	
Shale	470	560	
Shale & Shells	560	682	
Anhydrite	682	707	
Shale	707	1250	
Shale	1250	1330	
Shale & Lime	1330	1565	
Shale & Lime	1565	1575	
Shale & Lime	1575	1727	
Lime & Shale	1727	1855	Heebner 2866 (-1035)
Lime & Shale	1855	1992	Douglas Sand 2900
Shale & Lime	1992	2280	Brown Lime 2966 (-1135)
Shale & Lime	2280	2520	Lansing 2985 (-1154)
Lime & Shale	2520	2660	Sandy Congl. 3286 (-1455)
Lime & Shale	2660	2785	Arbuckle 3298 (-1467)
Lime & Shale	2785	2855	
Lime & Shale	2855	2954	
Lime & Shale	2954	2966	
Lime	2966	3020	
Lime	3020	3070	
Lime	2070	3145	
Lime	3145	3210	
Lime	3210	3260	
Lime	3260	3296	
Lime & Shale	3296	3307	
Lime	3307	3325	
Arbuckle	3325	3364	
Basal Sand	3365	3380	

RECEIVED
CORPORATION COMMISSION
OCT-6 1952
T.D. CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me this 29th day of August, 1951.

Oliver Carter

Notary Public

My commission expires March 21, 1955.

PLUGGING
FILE SEC 17 T 16 R 1124
BOOK PAGE 42 LINE 17