


WELL PLUGGING RECORD 15-009-07122-000

Give All Information Completely,  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barton County, Sec. 17 Twp. 16 Rge. 11 (E) (W)  
Location as "NE/CNW/SW" or footage from lines G NL NW NW  
Lease Owner Meltzer Oil Company  
Lease Name Oeser Well No. 4  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12/1/67 19\_\_\_\_  
Plugging completed 12/6/67 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1682 Feet  
3303'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	none
				4-1/2"	3281'	1682'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, ran sand to 3270' and dumped 4 sacks of cement. Loaded hole, shot pipe at 2655', 2542', 2083', 2014', 1950', 1885', 1816', 1753', 1683', worked pipe loose and pulled pipe. Bailed hole to 330', set 10' rock bridge, dumped 25 sacks of cement. Mudded to 40', set 10' rock bridge and dumped 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

DEC 11 1967  
12-11-67  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1967

My commission expires February 15, 1971

Margaret Mielcher  
Notary Public.

WEEKLY DRILLING REPORT

15-009-07122-0000

<b>WELL</b>	<b>J. T. GUNN</b>	<b>WELL</b>
(COMPANY)	<b>KRAFT-PROSA</b>	<b>ELEV.</b>
FROM <b>12-9</b> TO <b>12-18</b> 19 <b>48</b>	<b>DANBON</b>	<b>KANSAS</b>
	COUNTY PARISH	STATE

WELL DATA

DATE	DEPTH		FORMATION (FROM SAMPLES)	REMARKS
	FROM	TO		
12-9-48				Location staked 330' from North line & 670' from West line of NW/4 Section 17-15E-11W (ONE SW SW).
12-10-48 & 12-11-48 12-13-48				Location. Rigging collar & pits. Moving in rotary tools. Preparing location & rigging up. Rigging up rotary tools. Rigging up. Big muds. Mixed 13 sac Anagel.
12-14-48 12-16-48 12-15-48				SPUD 12-15-48. Morriston Drilling Co., Rotary Contractor.
	0	19 313 330	Surface soil & rock Shale & shells Sand	Mix 5 sac Anagel. Drilling 1 1/2" hole.
12-16-48	20	340 310	Shale & lime streaks Shale	Preparing to run surface casing. 3 5/8" O.D., 3/4" E thread, S.H. Logwell casing cemented a 340 with 200 sac & 4 1/2 Anagel; cement dis- solved. WOODS & rigging up. WOODS.
12-17-48	310	639	Shale & red bed	
12-18-48	639	700 735 1382	Shale & shells Anhydrite Shale & shells	Test 200' - 1 1/2" off. Test 1000' - 0".

CORRECT

**P. A. DOWD**  
EXPLORATION ENGINEER

APPROVED

**J. T. GUNN**  
SUPERINTENDENT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 1967

STATE CORPORATION DIVISION  
WICHITA, KANSAS