

15-009-20627-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Barton County. Sec 17 Twp. 16S Rge. 11W ~~XXX~~ ~~XXX~~
Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner M-G-M Oil Company
Lease Name Burmeister Well No. 1
Office Address 211 North Broadway, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25, 1971
Application for plugging filed Verbal Application 19
Application for plugging approved Verbal Approval 19
Plugging commenced October 25, 1971
Plugging completed October 25, 1971
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	329'	None

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 - 8 1971
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,290 feet (rotary total depth) to 480 feet. Set plug at 480 feet and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 480 feet to 300 feet. Set solid plug at 300 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud from 300 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sacks cement, two sacks cement in rathole. Plugging operations accomplished utilizing Allied Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dean Britting, Agent (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 North Main, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 5th day of November, 19 71



Elsie Willison
Notary Public.

My commission expires June 30, 1974

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-009-20627-0000

COMPANY **M-G-M Oil Company**

SEC. 17 T. 16S R. 11W

FARM **Burmeister**

NO. 1

LOC. **SW NE NE**

TOTAL DEPTH **3,290'**

COUNTY **Barton**


COMM. **October 19, 1971**

COMP. **October 25, 1971**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20	10		
15	8-5/8"	329'	cemented w/200 sxs cement ELEVATION 1811 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	10'
Post Rock	80'
Shale	340'
Shale and Red Bed	667'
Anhydrite	692'
Shale and Shells	920'
Shale	1,140'
Shale and Shells	1,490'
Lime and Shale	1,980'
Shale and Lime	2,680'
Lime and Shale	2,820'
Lime	3,290'
Rotary Total Depth	3,290'

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 8 1971
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 5th. day of November, 1971.

Elsie Willison
 Elsie Willison - Notary Public

Commission Expires:

June 30, 1974

