

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-009-22,560-000

LEASE NAME Oeser

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4290' Ft. from S Section Line

2970' Ft. from E Section Line

LEASE OPERATOR Davis Petroleum, Inc.

SEC. 17 TWP. 16 RGE. 11 (E) or (W)

ADDRESS Route 1, Box 183-B, Great Bend, Kansas 67530

COUNTY Barton

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 4656

Date Well Completed 10-29-81

Character of Well Oil

Plugging Commenced 12-08-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, Kansas Gib Scheck

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Kansas City Depth to Top 3111' Bottom 3208' T.D. 3318'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	303	8 5/8"	303'	0
	Production	0	3317	5 1/2"	3317'	2106'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
12-08-85: Set plug at 3100', dumped 4 sacks cement, shot casing at 2313', could not pull, shot casing at 2107', pulled 2106' of 5 1/2". 12-13-85: Halliburton pumped 7 sacks hulls and 175 sacks cement, pressured up to 1025 lbs. 1025 lbs max, shut in pressure 1025 lbs. Completed 11:45 am.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor D S & W Well Servicing, Inc. License No. 6901

Address P. O. Box 231, Claflin, Kansas 67525


STATE OF Kansas COUNTY OF Barton, ss.

X L. D. Davis (~~Employee of Operator~~) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis
(Address) L. D. Davis Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 85

X Bessie M. DeWerff
STATE CORPORATION Notary Public
My Commission Expires: 5-20-89 Bessie M. DeWerff



DEC 23 1985
12-23-85
CONS. DIVISION
Wichita, Kansas