

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-095-21792-0000
LEASE NAME A.R. Carrick
WELL NUMBER #6

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2310 Ft. from South Line of Section
2110 Ft. from East Line of Section

LEASE OPERATOR Messenger Petroleum, Inc. SPOT LOCATION 200'E of Nw Nw Se
ADDRESS 525 S. Main Section 32 Townshp 30s Range 8W
CITY, STATE, ZIP Kingman, Kansas 67068 County Kingman
PHONE # 316-532-5400 Date Well Completed August 3, 2001
Character of Well Abandoned due to Iron/Drill Collars/Bit in hole Date Plugging Commenced August 3, 2001
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 3, 2001

The plugging proposal was approved on August 3, 2001 at 3:00 pm (date)
by Steve VanGieson (KCC District Agent's Name)
Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 1619

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	95	and		
Redbeds	Shale	95	255	8-5/8"	241.98'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy mud from 1619' to 1575'. 7-7/8" bit and 6-3/8" drill collars from 1575' to 1510'. Heavy mud in hole. 35 sx cement @ 1510', 35 sx @ 900', 35 sx @ 300' 11:00 pm on 8/3/01 by Allied, ticket # 5860.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Drilling Company (Agent)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 6th day of Aug., 192001

RECEIVED

AUG 7 2001
8-7-01
KCC WICHITA

NOTARY PUBLIC - State of Kansas
PAMELA S. FIELDS
My Appt. Exp. 1-28-05

Pamela S. Fields
(Notary Public)

My Commission Expires:

Form CP-4
Revised 12-92

OR

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

A.R. Carrick #6

LOCATION: 200'E of Nw Nw Se
API: 15-095-21792-0000

Section 32 T 30s R 8w
Kingman County, Kansas

OWNER: Messenger Petroleum, Inc.

COMMENCED: 31-Jul-01

CONTRACTOR: Sterling Drilling Company, Rig #4

COMPLETED: 03-Aug-01

TOTAL DEPTH: DRILLER 1619 FEET
LOGGER Not Logged FEET

Ground Elevation: 1677
KB Elevation: 1686

LOG

0 -	95 FEET	Top Soil and Water Sands
95 -	950 FEET	Redbeds
950 -	1550 FEET	Shales and Salt
1550	1619 FEET	Shale/Limestone/Chert and Sandstone

CASING RECORDS

Spud @ 7:30 am on 07-31-01. Drilled 12-1/4" hole to 255'. Ran 6 joints of 20# 8-5/8" surface casing 241.98' set at 253' KB. Cemented with 175 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 12:15 pm on 07-31-01 by Allied. Good returns. Ticket # 8123.

PLUGGING RECORDS

Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy mud from 1619' to 1575'. 7-7/8" bit and 6-3/8" drill collars from 1575' to 1510'. Heavy mud in hole. 35 sx cement @ 1510', 35 sx @ 900', 35 sx @ 300' and 25 sx from 60' to surface. Plugged mousehole with 10 sx and rathole with 15 sx. Job completed at

DEVIATION SURVEYS

0 degree(s) at 255 feet

RECEIVED

AUG - 7 2001

KCC WICHITA