

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-117

API NUMBER 15-095-21795-0000  
LEASE NAME A.R. Carrick  
WELL NUMBER #7

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

2310 Ft. from South Line of Section  
2060 Ft. from East Line of Section

LEASE OPERATOR Messenger Petroleum, Inc. SPOT LOCATION 80' W of N/2 Nw Se  
ADDRESS 525 S. Main Section 32 Township 30s Range 8w (W)  
CITY, STATE, ZIP Kingman, Kansas 67068 County Kingman  
PHONE # 316-532-5400 Date Well Completed August 14, 2001  
Character of Well D & A Date Plugging Commenced August 14, 2001  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 14, 2001

The plugging proposal was approved on August 13, 2001 at 8:45 am (date)  
by Virgil Clothier (KCC District Agent's Name)  
Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4444

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION              | CONTENT     | FROM | TO  | SIZE   | PUT IN  | PULL OUT |
|------------------------|-------------|------|-----|--------|---------|----------|
| Surface Soil and Sands | Water sands | 0    | 100 | and    |         |          |
| Redbeds                | Shale       | 100  | 255 | 8-5/8" | 242.27' | 0'       |
|                        |             |      |     |        |         |          |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy mud in hole. Bottom plug @ 1400' with 35sx,  
2nd plug @ 950' with 35sx, 3rd plug @ 300' with 35sx, top plug @ 60' with 25sx cemented to surface,  
Plug down at 10:00 am on 08-14-01 by Allied. Good returns. Ticket # 7942. Plugged rathole  
with 15sx, mousehole with 10sx.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sterling Drilling Company (Agent)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 17<sup>th</sup> day of August, 19 2001



Irene F. Shumway  
(Notary Public)

RECEIVED

My Commission Expires: July 8, 2005

AUG 20 2001

KCC WICHITA

RECEIVED  
ST. CORPORATION COMMISSION  
AUG 20 2001  
8-20-01  
Conservation Division  
Wichita, Kansas

Form CP-4  
Revised 12-92

OR

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

## SAMPLE LOG

A.R. Carrick #7

**LOCATION:** 80' W of N/2 Nw Se  
**API:** 15-095-21795-0000

Section 32 T 30s R 8w  
Kingman County, Kansas

**OWNER:** Messenger Petroleum, Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 06-Aug-01  
**COMPLETED:** 14-Aug-01

**TOTAL DEPTH:** **DRILLER** 4444 FEET  
**LOGGER** 4441 FEET

**Ground Elevation:** 1677  
**KB Elevation:** 1686

## LOG

|       |           |                                     |
|-------|-----------|-------------------------------------|
| 0 -   | 100 FEET  | Top Soil and Water Sands            |
| 100 - | 950 FEET  | Redbeds                             |
| 950 - | 1550 FEET | Shales and Salt                     |
| 1550  | 4444 FEET | Shale/Limestone/Chert and Sandstone |

## CASING RECORDS

Spud @ 7:15 am on 08-06-01. Drilled 12-1/4" hole to 255'. Ran 6 joints of new 20# 8-5/8" surface casing 242.27' set at 253' KB. Cemented with 160 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 11:15 pm on 08-06-01 by Allied. Good returns. Ticket # 8208.

## PLUGGING RECORDS

Plugged hole using 155 sx 60/40 Poz 4% Gel. Heavy mud in hole. Bottom plug @ 1400' with 35sx, 2nd plug @ 950' with 35sx, 3rd plug @ 300' with 35sx, top plug @ 60' with 25sx cemented to surface. Plug down at 10:00 am on 08-14-01 by Allied. Good returns. Ticket # 7942. Plugged rathole with 15sx, mousehole with 10sx.

## DEVIATION SURVEYS

3/4 degree(s) at 255 feet

RECEIVED

AUG 20 2001

KCC WICHITA