

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24520 -0000

LEASE NAME SAUBER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 Ft. from (S) Section Line

4290 Ft. from (E) Section Line

SEC. 16 TWP. 16 SRGE. 11 (E) or (W)

COUNTY Barton

LEASE OPERATOR HAR-KEN Oil Company

ADDRESS 2932 NW 122nd, Unit 15 Oklahoma City, OK 73120

PHONE# (405) 752-0318 OPERATORS LICENSE NO. 9911

Date Well Completed 7-30-92

Character of Well D&A

Plugging Commenced 7-30-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-30-92

The plugging proposal was approved on July 30, 1992 (date)

by Ed Shoemaker (KCC District Agent's Name).

Is ACO-1 filed? by operator if not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	386	8 5/8"	386	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

20 sx. @ 3325', 20 sx. @ 720', 90 sx. @ 435', 10 sx. @ 40', 15 sx. in rat hole
Total 155 sx. 60/40 Pozmix, 6% Gel 1/4# flo seal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HAR-KEN Oil Company

STATE OF KANSAS COUNTY OF BARTON, ss.

C.L. D. Davis (Employee of Operator) RECEIVED (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well as filed that statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature] AUG 7 1992

(Address) R.R. 1 Box 183 B 8-7-92

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 92

[Signature]
Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93



15-009-245200000

DRILLER'S WELL LOG

COMMENCED: 7-23-92
COMPLETED: 7-30-92

HAR-KEN Oil Company
SAUBER #1
NE NW SW Sec. 16-T16S-R11W
Barton County, Kansas

0 - 387 Rock & Shale
387 - 1335 Shale
1335 - 3195 Lime
3195 - 3306 Lime & Shale
3306 - 3375 Lime & Cong.

ELEVATION: 1860 GR 1865 KB

FORMATION DATA:

Anhy. 716 (+1149)
Topeka 2608 (-743)
Heebner 2902 (-1037)
Toronto 2923 (-1058)
Douglas 2938 (-1073)
Brown Lime 2998 (-1133)
Lansing 3016 (-1151)
Arbuckle 3318 (-1453)
RTD 3375 (-1510)

SURFACE CASING:

8 5/8" set @ 386 W/175 sx. 40/60
Pozmix, 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss

GEO. D. DAVIS of lawful age, does swear and state that the facts and statements
herein are true and correct to the best of his knowledge.

Geo. D. Davis
GEO. D. DAVIS

Subscribed and sworn to before me this 5th day of August, 1992



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1992

CONSERVATION DIVISION
Wichita, Kansas