


15-009-05818-0000

STATE OF KANSAS
CORPORATION COMMISSION
Give All Formations Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 19 Twp. 16 Rge. 11 (E) (W)
 Location as "NE/CNW/SW" or footage from lines NE 34 SW
 Lease Owner Sol Robinowitz NW 32
 Lease Name Hoffman Well No. B-1
 Office Address 311 Shell Building, Tulsa, Oklahoma
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed June 24, 1958 19
 Application for plugging filed June 24, 1958 19
 Application for plugging approved _____ 19
 Plugging commenced June 24, 1958 19
 Plugging completed June 24, 1958 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leiker
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3366 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PWT IN	PULLED OUT
		0'	313'	8 5/8"	313'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 310'. Set bottom plug at 310' with 20 sacks cement. Filled hole with heavy mud to 40' and set plug at 40' and cemented with 10 sacks cement and 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company
 Address P. O. Box 123, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Cecil M. Olson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C Olson
P. O. Box 123, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 19 58

My commission expires June 24, 1959

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1958
6-28-58
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 19 T. 16 R. 11W
BOOK PAGE 111 LINE 19

WELL LOG

15-09-05818-000

Date Started: June 12, 1958
Date Completed: June 23, 1958

Hoffman B-1
NE 1/4 SW
Section 19-16-11
Barton County, Kansas

	Elevation	1911' K.B.
Anhydrite	765'	1146
Heebner	2967'	-1046
Brown Lime	3053'	-1142
Lansing	3067'	-1156
Conglomerate	3331'	-1420
R.T.D.	3366'	-1455

8 5/8" set at 313'

0' - 40'	Surface Clay and Rock
40' - 60'	Shale and Rock
60' - 110'	Shale
110' - 120'	Sand
120' - 180'	Shale and Sand Streak
180' - 225'	Shale
225' - 240'	Sand
240' - 275'	Shale
275' - 280'	Sand
280' - 313'	Shale
313' - 372'	Shale
372' - 480'	Sand
480' - 490'	Shale
490' - 517'	Sand and Iron
517' - 575'	Shale and Sand Streak
575' - 765'	Shale and Red Bed
765' - 789'	Anhydrite
789' - 1085'	Shale and Shell
1085' - 1370'	Shale and Shell
1370' - 1470'	Salt and Shale
1470' - 1750'	Shale and Shells
1750' - 2000'	Lime and Shale
2000' - 2490'	Lime and Shale
2490' - 2635'	Lime and Shale
2635' - 2770'	Lime
2770' - 2957'	Lime
2957' - 3025'	Heebner
3025' - 3067'	Lime
3067' - 3120'	Lansing
3120' - 3215'	Lime
3215' - 3331'	Lime
3331' - 3366'	Conglomerate
3366'	R.T.D.

AFFIDAVIT

State of Kansas County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: C. Olson

Subscribed and sworn before me this 27th day of June, 1958.

Carl E. Stinson
NOTARY PUBLIC

My commission expires: June 24, 1959.

PLUGGING				
FILE	SEC	19 T. 16 R. 11W		
BOOK	PAGE	111	LINE	19

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1958
CONSERVATION DIVISION
Wichita, Kansas