

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Give All Information Completely
No Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
809 Bittling Building
Wichita, Kansas

Stafford County, Sec. 30 Twp. 24S Rge. 12 (E) 12 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330'S & 330'E of W/4 Corner

Lease Owner Continental Oil Company

Lease Name C. V. Gline Well No. 1

Office Address Box 1267, Ponca City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed March 19, 19 42

Application for plugging filed March 19, 19 42

Application for plugging approved March 20, 19 42


Plugging commenced March 20, 19 42

Plugging completed March 20, 19 42

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production No production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. C. T. Alexander

Producing formation Arbuckle Lime Depth to top 4160' Bottom 4221' Total Depth of Well 4221 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	440'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Hole was filled with heavy mud to within 440' of the top, a wood plug was set at this depth and cemented with 15 sacks of cement, the hole was then filled to within 33' of the top with heavy mud, a wood plug was set at this depth and cemented with 15 sacks of cement, the hole was then filled with heavy mud to the top and a steel cap welded over the 10-3/4" casing.

pd
4 3/4
HO
Casing
30 24 12 W
LOOK 28 11 18

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Continental Oil Company

Address c/o F. L. Dunn, R. F. D. #4, Lyons, Kansas

4-11-42

STATE OF Kansas, COUNTY OF Rice, ss.

F. L. Dunn

(employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

F. L. Dunn

R. F. D. #4, Lyons, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 7th day of April 19 42

Louis M. Gine

Notary Public.

My commission expires October 21, 1944



C. V. OLINE No. 1

Date Spudded: March 1, 1942
 Drig. Completed: March 19, 1942
 Date Plugged: March 20, 1942

Loc: 330' S & 330' E of W/4 Corner
 of Sec. 30, Twp. 24S, Rge. 18W,
 Stafford County, Kansas

From	To	Formation	From	To	Formation
0	130	Shale & sand	3010	3050	Broken lime
130	443	Shale & shells	3050	3164	Lime
443	750	Shale & red bed	3164	3170	Shale & shells
750	770	Anhydrite	3170	3454	Lime
770	1280	Shale & shells	3454	3560	Lime & shale
1280	1350	Salt	3560	3585	Shale & shells
1350	1400	Shale	3585	3690	Lime
1400	1635	Shale & shells	3690	3720	Lime & chert
1635	1770	Shale & lime	3720	3907	Lime
1770	1825	Lime	3907	3952	Cherty lime
1825	1860	Shale & lime	3952	4003	Shale
1860	1940	Broken lime	4003	4030	Lime
1940	1950	Lime	4030	4062	Lime chert
1950	2040	Shale & shells	4062	4082	Lime & chert
2040	2120	Lime	4082	4110	Lime, chert
2120	2240	Lime & shale	4110	4115	Broken lime & shale
2240	2305	Broken lime	4115	4160	Shale & lime
2305	2405	Shale & shells	4160	4165	Lime & chert
2405	2652	Broken lime	4165	4225	Lime
2652	3010	Shale & shells		4221'	Total depth from ground level.

Elevation 1906'

Run 440' of 10-3/4" OD 28# 3 ga. "Armco" spiral weld casing; set at 437'; cemented with 340 sacks of cement.

Top of Viola Lime 4003'

Top of Simpson Sand 4102'

Top of Arbuckle Lime 4160'

Cored from 4161' to 4171', recovering 2', good porosity, no show of oil.

Well drilled to a total depth of 4221' finding no show of oil.

Plugged and abandoned March 20, 1942.

Total depth 4221'

Note: All of above footages are calculated from the ground level.

FLD-JL 4/7/42
 LPC (3) JWC (2) File (1)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

F. L. D.
 Name and title of representative of company

Subscribed and sworn to before me this the 7th day of April, 1942

My Commission expires 10-21-1944

Lewis M. Lane
 Notary Public

INDEXING
 FILE 20 24-12W
 BOOK 28 18

STATE OF KANSAS
 APR 11 1942