

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-185-22,208-000c

LEASE NAME McMillan

WELL NUMBER 1-19

SPOT LOCATION C SW $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$

SEC. 19 TWP 24 SRGE. 12 W~~XXXX~~ (W)

COUNTY Stafford

Date Well Completed 4-24-85

Plugging Commenced 4-24-85

Plugging Completed 4-24-85

LEASE OPERATOR Rine Exploration Company
ADDRESS Suite 645, 300 W. Douglas
Wichita, KS 67202

PHONE # (316) 262-5418 OPERATORS LICENSE NO. 5020

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4180

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	shale	0	305	8-5/8"	203	none
cemented with 200 sx common, 2% gel, 3% cc, plug down at 11:45 a.m. 4-16-85 by Allied; cement did circ.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged as follows by Allied with 60/40 posmix 2% gel, 3% cc;
15 sx in rat hole; 50 sx @ 720'; 40 sx @ 330'; 10 sx @ 40' w/solid
bridge plug; job completed at 4 a.m. 4-24-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Drilling Co., Inc. License No. 5137
Address 200 E. First, Suite 500
Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

MAY 13 1985

Jon T. Williams, Jr. (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 200 E. First, Suite 500
Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 24 day of April, 19 85

My Commission expires: 1-14-89.

Gerri M. Stewart
Notary Public
Gerri M. Stewart