

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

X			

Locate well correctly on above
Section Plat

Stafford County. Sec. 18 Twp. 24 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Robinowitz Oil Company
Lease Name McMillan Well No. 1
Office Address 311 Shell Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 8-23 19 59
Application for plugging filed 8-23 19 59
Application for plugging approved 8-23 19 59
Plugging commenced 8-23 19 59
Plugging completed 8-23 19 59
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4107 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe		-0-	263'	8 5/8	263	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud.
Set plug at 240'. Mixed and dumped 20 sacks
cement on top.
Set plug at 35'. Mixed & dumped 10
sacks cement on top.

RECEIVED
STATE CORPORATION COMMISSION
SEPT 1 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor A. L. Jackson, Drilling Company
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
C. L. Miles, partner of Contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Miles

Box 194, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of August, 19 59

Rick D. Cowan

Notary Public.

My commission expires 6-9-63

PLUGGING
C. L. Miles, partner of Contractor
PAGE 1 LINE 2

WELL LOG
Mc Millan # 1
SW SW NW 18-24-12
Stafford County, Kansas

0 - 60	Surface soil	Elevation: 1897' KB
60 - 263	Sand and shale	
263 - 505	Red bed	
505 - 715	Shale and red bed	
715 - 755	Anhydrite	
755 - 1480	Shale and shells	Formation Tops
1480 - 1630	Shale	Brown Lansing 3501'
1630 - 1805	Fort Riley lime	White Lansing 3528'
1805 - 2120	Lime	Base Kansas City 3798'
2120 - 2270	Lime and shale	Conglomerate 3843'
2270 - 2400	Shale - lime streaks	Kinderhook 3877'
2400 - 3085	Lime and shale	Viola 3900'
3085 - 3190	Lime	Simpson 4028'
3190 - 3345	Lime and shale	Arbuckle 4090'
3345 - 3375	Lime	
3375 - 3585	Lime and shale	
3585 - 3898	Lime	
3898 - 3938	Lime and chert	
3938 - 3983	Viola chert	
3983 - 4088	Lime	
4088 - 4089	Shale and lime	
4089 - 4107	Arbuckle	
4107	T D	

RECEIVED
STATE OF KANSAS

SEP 1 1959

CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS
COUNTY OF BARTON ss

C. L. Miles, partner of A. L. Jackson Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

C. L. Miles

C. L. Miles

Subscribed and sworn before me this 27 day of August, 1959.

Dick L. Claus

Notary Public Barton County

My Commission Expires: 5-9-63

RECEIVED
STATE OF KANSAS

SEP 1 1959

CONSERVATION DIVISION
Wichita, Kansas

