

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Stafford County. Sec. 16 Twp. 24 Rge. 13 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Mallard Drilling Company
Lease Name Delp Well No. 1
Office Address 1016 Union National Bank
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed July 1 19 50
Application for plugging filed " 19 50
Application for plugging approved " 19 50
Plugging commenced " 19 50
Plugging completed " 19 50
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes--oral

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4158 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled Out
				3 5/8	312	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full heavy mud to 312 feet,
drove wooden plug to 312 feet and dumped in 15
sacks cement, finished filling hole full
heavy mud to within 30 feet of cellar
and dumped 10 sacks cement.

77-50

RECEIVED

Cons. Div.

JUL 7 - 1950

STATE CORPORATION
COMMISSION


KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mallard Drilling Company
Address 1016 Union Natl. Bank, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. C. Nelson, partner (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. C. Nelson

SUBSCRIBED AND SWORN to before me this 6th day of July, 1950
My commission expires 12/4/52
Notary Public.



COMPANY: Mallard Drilling Company
 CONTRACTOR: Mallard Drilling Company
 FARM: Delp #1
 LOCATION: SW SW NE
 Sec. 16-24-13, Stafford County, Kansas
 COMMENCED: June 19, 1950
 COMPLETED: June 30, 1950

0	to	40	Surface sand
40	to	130	Sand and shale
130	to	312	Shale and shells
312	to	940	Red bed and shale
940	to	1500	Shale and shells
1500	to	1735	Lime and shale
1735	to	1870	Lime
1870	to	2280	Lime
2280	to	2390	Lime
2390	to	2740	Shale and lime
2740	to	3150	Shale and lime
3150	to	3290	Shale and lime
3290	to	3470	Lime
3470	to	3559	Shale and lime
3559	to	3580	K.C. Lime
3580	to	3645	Lime
3645	to	3685	Lime
3685	to	3750	Lime
3750	to	3810	Lime
3810	to	3885	Lime
3885	to	3924	Lime--chert
3924	to	3942	Viola lime
3942	to	3981	Viola lime
3981	to	4023	Lime
4023	to	4063	Lime
4063	to	4066	Lime
4066	to	4113	Simpson
4113	to	4158	Arbuckle
		4158	T. D.

Set 312 feet of 8 5/8" surface pipe. Cemented with 225 sacks cement.

TOPS: 3553--K.C. Conglomerate--3911 Viola--3924 Simpson--4066
 Arbuckle--4117

DRY, ABANDONED AND PLUGGED.

Measurements taken from derrick floor.

JUL 7 - 1950
 ST. COLUMBIA
 KANSAS

Certificate

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Delp #1, Sec. 16-24-13, Stafford County, Kansas, as reflected by files of the Mallard Drilling Company.

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County Kansas, this 6th Day of July 1950.

My commission expires 12/4/52

PLUGGING
 SEC. 16-24-13
 DICK PAGE 14 LINE 18