


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 16 Twp. 24S Rge. 13W (EX) (W)

Location as "NE/CNW/SW" or footage from lines S $\frac{1}{2}$ S $\frac{1}{2}$ SW $\frac{1}{4}$
Lease Owner: Leben Drilling, Inc.
Lease Name: Irons Well No. 1
Office Address: 905 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-18-58 19
Application for plugging filed 9-18-58 19
Application for plugging approved 9-18-58 19
Plugging commenced 9-18-58 19
Plugging completed 9-18-58 19
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4135 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	239'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set @ 210' with 1/4 sack hulls & 20 sx. cement,
filled up with mud to 35', set plug w/10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September 19 58

My commission expires June 17, 1961

Ruth N. Benjamin
Notary Public.

PLUGGING
FILE SEC 16 T 24 R 3W
BOOK PAGE 132 LINE 38

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1958
DIVISION

DELLER'S LOG

COMPANY:
CONTRACTOR:
WELL:
LOCATION:

CONCEIVED:
COMPLETED:

LEHEN DRILLING, INC.
LEHEN DRILLING, INC.
LENS #1
S $\frac{1}{2}$ S $\frac{1}{2}$ SW $\frac{1}{4}$ SEC. 16-24S-13W
STAFFORD COUNTY, KANSAS
SEPTEMBER 5, 1958
SEPTEMBER 18, 1958

0	20	Surface Clay & Sand	
20	160	Sand	
160	245	Shale	
245	775	Sand, Shale, Red Bed	LOG TOPS:
775	805	Anhydrite	Anhydrite 710
805	825	Shale	Heater 2401
825	1200	Shale & Shells	Leavenworth 2407
1200	1625	Shale	Toronto 2422
1625	1845	Shale & Lime	Douglas 2444
1845	1960	Lime	Br. Lime 3539
1960	2140	Lime & Shale Streaks	Lansing 3560
2140	2230	Lime & Shale	Br. K. C. / 3833
2230	2370	Shell & Shale	Viola 3910
2370	2470	Shale with Lime	Gleason Shale 4068
2470	2880	Shale & Shells	Artuckle 4115
2880	3015	Shale	
3015	3195	Shale & Shells	ELEVATION 1926 K.B.
3195	3665	Lime & Shale	
3665	4025	Lime	
4025	4115	Lime	
4115	4125	Artuckle	
	4125	Rotary Total Depth - D. & A.	

Set 237' of 8 5/8" surface casing with 200 sacks cement & 2% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lens #1, located S $\frac{1}{2}$ S $\frac{1}{2}$ SW $\frac{1}{4}$ of Section 16, Township 24 South, Range 13 West, Stafford County, Kansas, as reflected by the files of Lehen Drilling, Inc.

LEHEN DRILLING, INC.

Frank Hamlin
Frank Hamlin

OCT 28 1958

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, in and for Sedgewick County, Kansas, this 24th day of September, 1958.

Ruth H. Benjamin
Ruth H. Benjamin, Notary Public

My Commission Expires: June 17, 1961.

PLUGGING			
FILE	SEC	T. 24	R. 13W
BOOK	PAGE	132	LINE 38